



## Levin-Richmond Terminal Corporation

402 Wright Avenue, Richmond, California 94804

Tel. (510) 307-4000 / Fax. (510) 236-0129

August 31, 2017

Ms. Karen Jurist  
United States Environmental Protection Agency Region 9  
75 Hawthorne Street  
San Francisco, California 94105  
Via email: [jurist.karen@epa.gov](mailto:jurist.karen@epa.gov)

RE: 2016-2017 Annual Report, United Heckathorn Superfund Site, Upland Capping System  
Richmond, California

Dear Ms. Jurist:

Enclosed please find the 2016-2017 Annual Report for the Upland Capping System at the United Heckathorn Superfund Site.

Please feel free to contact me if you have any questions or concerns with the attached report.

Sincerely,

Jim Holland  
Vice President of Facilities, Equipment, and Environmental  
Officer  
Levin Richmond Terminal Corporation  
(510) 307-4076

Enclosure: 2016-2017 Annual Report for United Heckathorn Superfund Site Upland Capping System



# 2016-2017 Annual Report

**United Heckathorn Superfund Site  
Upland Capping System  
Richmond, California**

August 31, 2017  
Rev. 0

*prepared for:*

**Levin Richmond Terminal Corporation**  
402 Wright Avenue  
Richmond, California 94804



# 2016-2017 Annual Report

**United Heckathorn Superfund Site  
Upland Capping System  
Richmond, California**

August 25, 2017  
Rev. 0

*prepared by:*

**CDIM Engineering, Inc.**  
45 Polk Street, 3<sup>rd</sup> Floor  
San Francisco, CA 94102

CDIM's work for the Levin Richmond Terminal Corporation was conducted under my supervision. To the best of my knowledge, the data contained herein are true and accurate, are based on what can be reasonably understood as a result of this project, and satisfy the scope of work prescribed by the client for this project. The data, findings, recommendations, specifications, or professional opinions were prepared solely for the use of the Levin Richmond Terminal Corporation in accordance with generally accepted professional engineering and geologic practice. We make no other warranty, either expressed or implied, and are not responsible for the interpretation by others of the contents herein.



A handwritten signature in blue ink that reads "Scott Bourne".

Scott Bourne, PE #C72817  
Principal Engineer

August 31, 2017

Date

## TABLE OF CONTENTS

<b>1</b>	<b>INTRODUCTION</b>	<b>1</b>
1.1	Background	1
1.2	Program Objectives	1
1.3	Operation and Maintenance Program	2
1.4	Contents of this Report	2
<b>2</b>	<b>SITE DESCRIPTION</b>	<b>3</b>
2.1	Upland Area Description and Current Use	3
2.2	Nearby Water Bodies	3
2.3	Upland Area Cap	3
2.4	Storm Water Collection and Advanced Treatment	3
<b>3</b>	<b>OPERATION AND MAINTENANCE</b>	<b>5</b>
3.1	Upland Cap Maintenance	5
3.2	Storm Water Collection System Inspection and Cleaning	5
3.3	Storm Water Monitoring	5
	3.3.1 Storm Water Sampling	5
	3.3.2 Sample Results	6
	3.3.3 Quality Assurance/Quality Control	7
	3.3.4 Assessment of Results	7
3.4	Storm Water Treatment System Operation	8
<b>4</b>	<b>ANNUAL SITE INSPECTION</b>	<b>9</b>
4.1	Concrete Cap Inspection	9
4.2	Gravel Cover Inspection	9
4.1	Triennial Upland Cap Survey	10
<b>5</b>	<b>PROPOSED SITE WORK FOR 2017-2018</b>	<b>11</b>
<b>6</b>	<b>CONCLUSIONS AND RECOMMENDATIONS</b>	<b>12</b>
<b>7</b>	<b>REFERENCES</b>	<b>13</b>



## **TABLES**

Table 1	2016-2017 Annual Storm Water Sampling Data for Pesticides
Table 2	2016-2017 Annual Storm Water Sampling Data for General Parameters and Metals
Table 3	Proposed Site Work for 2017-2018

## **FIGURES**

Figure 1	Site Location Map
Figure 2	Site Layout
Figure 3	Upland Area Photo Locations and Maintenance Recommendations
Figure 4	Treatment System TS2 Total DDT, 2015-2017

## **APPENDICES**

Appendix A	Upland Capping System Inspection Photographs
Appendix B	Laboratory Analytical Reports
Appendix C	Upland Capping System Inspection Form
Appendix D	Upland Cap Survey Plat

## ACRONYMS AND ABBREVIATIONS

BMP	best management practices
CDIM	CDIM Engineering, Inc.
DDD	dichlorodiphenyldichloroethane
DDE	dichlorodiphenyldichloroethene
DDT	dichlorodiphenyltrichloroethane
EPA	United States Environmental Protection Agency
gpm	gallons per minute
Heckathorn site or Site	United Heckathorn Superfund Site
IGP	Storm Water Industrial General Permit
LRT	Levin Richmond Terminal
LRTC	Levin Richmond Terminal Corporation
MDL	method detection limit
MLLW	mean lower low water
msl	mean sea level
NAL	numeric action level
NPDES	National Pollutant Discharge Elimination System
O&G	oil and grease
O&M	operations and maintenance
O&M Plan	<i>Revised Draft Operations and Maintenance Plan, Upland Capping System, Former United Heckathorn Site</i>
pg/L	picograms per liter
ROD	Record of Decision
SWPPP	Storm Water Pollution Prevention Plan
SWRCB	State Water Resource Control Board
Third Five-Year Review	<i>Third Five-Year Review Report for United Heckathorn Superfund Site, Richmond, California</i>
TS-2	advanced storm water treatment system TS-2
TSS	total suspended solids
µg/L	micrograms per liter

## 1 INTRODUCTION

On behalf of the Levin Richmond Terminal Corporation (LRTC), CDIM Engineering, Inc. (CDIM) prepared this 2016-2017 Annual Report to describe inspection, monitoring, and maintenance performed on the upland cap at the United Heckathorn Superfund Site (the Heckathorn Site).

### 1.1 Background

From 1947 through 1966, the Heckathorn Site was used for formulation, processing, packaging, and shipping of pesticides including aldrin, dichlorodiphenyltrichloroethane (DDT), dieldrin, and endrin. These activities resulted in the release of pesticides to the surrounding soils and to the Lauritzen Channel. In 1994, after remedial investigation and feasibility studies were completed, the United States Environmental Protection Agency (EPA) adopted a Record of Decision (ROD) for remedial action requiring:

- Dredging of all soft bay mud from the Lauritzen Channel and Parr Canal, with offsite disposal of dredged material;
- Placement of clean material after dredging;
- Construction of a cap at and around the former Heckathorn facility to prevent erosion;
- A deed restriction limiting the property at the former Heckathorn facility location to non-residential uses; and,
- Marine monitoring to verify the effectiveness of the remedy (EPA, 1994b).

In 1996, LRTC entered a Consent Decree<sup>1</sup> with the EPA, which outlined LRTC's responsibility to design, construct, and maintain a concrete cap at and around the former Heckathorn facility to prevent erosion (United States District Court, 1996a). LRTC completed construction of the concrete cap in July 1999 (PES, 1999b.)

Since the cap was constructed, EPA has completed four five-year reviews and has found the upland remedial action is functioning as intended, is protective of human health and the environment, and has met the remedial action objective for the upland area due to capping of contaminated soils, which has eliminated human exposure pathways and prevented erosion (EPA, 2016a).

### 1.2 Program Objectives

In order to ensure long-term protection of human health and the environment, the remedial action goal established by the EPA for upland and embankment soils is the prevention of erosion and transport into the Lauritzen Channel (EPA, 1994a).

---

<sup>1</sup> Montrose Chemical Corporation of California, Chris-Craft Industrial, Rhone-Poulenc, Inc. and Stauffer Management Company (collectively the "Montrose Group") entered into a separate Consent Decree with EPA for dredging of young bay mud from the Lauritzen Channel and Parr Canal, with offsite disposal of dredged material and placement of clean fill after dredging (United States District Court, 1996b).

The upland cap was designed to prevent the release of residual chlorinated pesticides that are present in soils (PES, 1998).

The objective of the cap inspection and storm water monitoring programs is to identify any potential release of pesticide-impacted soil by examining the integrity of the cap system through visual inspection and storm water monitoring (EPA, 2011).

### 1.3 Operation and Maintenance Program

LRTC performs operations and maintenance (O&M) activities in accordance with the *Revised Draft Operations and Maintenance Plan, Upland Capping System, Former United Heckathorn Site* (O&M Plan; PES, 1999a). LRTC performs additional O&M activities recommended by EPA in the *Third Five-Year Review Report for United Heckathorn Superfund Site, Richmond, California* (Third Five-Year Review; EPA, 2011) to provide added confidence that the upland area remedy maintains its effectiveness.

### 1.4 Contents of this Report

This Annual Report describes activities performed by LRTC to inspect, monitor and maintain the upland cap for the period of July 1, 2016 to June 30, 2017. Included is a summary of each of the following:

- Capping system maintenance activities;
- Storm water collection system inspection and cleaning;
- Storm water system monitoring;
- Storm water treatment;
- Triennial cap survey;
- Annual cap inspection;
- Proposed site work for 2017-2018; and,
- A conclusion with CDIM's opinion as to the overall condition and effectiveness of the cap in meeting the program objectives.

## 2 SITE DESCRIPTION

The Levin Richmond Terminal (LRT) is located at 402 Wright Avenue in Richmond, California and is immediately adjacent to the Lauritzen Channel in the Richmond Harbor (Figure 1). The Heckathorn Site includes the northern five acres of the Main Terminal at LRT, known as the upland cap area (Figure 2).

### 2.1 Upland Area Description and Current Use

The upland cap area is bounded by a railroad track and Cutting Boulevard to the north; South Fourth Street to the east; the LRT and Santa Fe Channel to the south; and, the Lauritzen Channel to the west. The majority of the upland cap area is relatively flat with surface elevations of approximately 9 feet above mean sea level (msl), with the exception of the portion of the upland cap area north of the Lauritzen Channel, which was raised to approximately 15 feet above msl during cap construction.

The upland cap area is used primarily for storage of dry bulk product and railroad operations. Photographs taken during the site inspection are included in Appendix A.

### 2.2 Nearby Water Bodies

The storm water system in the upland cap area discharges directly to the Lauritzen Channel (Figure 2). The Lauritzen Channel is connected to the San Francisco Bay via the Santa Fe Channel and Richmond Inner Harbor.

### 2.3 Upland Area Cap

Construction of the concrete cap at the upland cap area began in July 1998 and was completed in July 1999 (PES, 1999b). Installation of the cap consisted of: (1) site grading to promote surface runoff to collection points; (2) installation of a drainage system to collect surface runoff, including best management practices (BMPs) for storm water pollution prevention; and (3) construction of a reinforced concrete cap in the majority of the 5-acre area and construction of a geotextile fabric and gravel cap in the railroad track area (Figure 2). The concrete cap consists of a minimum 6-inch thick concrete with a double layer of welded wire fabric reinforcement. The gravel cover consists of a geotextile fabric over a prepared subgrade. The geotextile fabric is covered by a 6-inch layer of gravel.

### 2.4 Storm Water Collection and Advanced Treatment

The facility is paved with asphalt and concrete and is graded to direct surface water runoff via sheet flow or shallow swales to drop inlets (Figure 3). The drop inlets drain to five below-grade interceptors<sup>2</sup> (SW-3 through SW-7) via underground pipe. The interceptors are equipped with compartments and steel baffles to allow the

---

<sup>2</sup> The interceptors design was based on a five-minute retention time during a 10-year, 24-hour storm event (PES, 1999a).

settling of sediments and separation of oil/grease and floatables, and also with normally-closed gate valves at the effluent pipe, which can be opened during heavy rains to enable discharge to the Lauritzen Channel.

In 2015, LRTC completed modifications<sup>3</sup> to the upland cap area storm water collection system and installation of advanced storm water treatment system TS-2 (TS-2). Single-speed submersible pumps placed into final chamber of each interceptor were connected to newly installed storm drain pipe along the edge of the LRTC pier. During storm events, the submersible pumps push storm water captured by interceptors SW-3 to SW-7 through an inline static mixer where a biopolymer flocculant is added. Storm water then flows into a series of two 21,000-gallon aboveground clarification tanks, where the flocculant and solids separate from the water. Storm water overflows from the second clarifier and is pumped through four, 48-inch diameter sand filters. Effluent from the treatment system then is discharged to the Lauritzen Channel at the interceptor SW-5 outfall. TS-2 is equipped with variable speed drive for pump control, a programmable logic controller, and a human machine interface.

The estimated flow for the SW-3 to SW-7 catchments that results from a 0.2 inches per hour design storm intensity<sup>4</sup> is approximately 500 gallons per minute (gpm). TS-2 is designed to treat approximately 650 gpm, or approximately 130% of the IGP-required flow. Additionally, due to the storage volume provided by interceptors, clarifiers and equalization tank, the system is able to capture and treat periods of storm water flow in excess of 650 gpm before treatment bypass occurs.

---

<sup>3</sup> The storm water treatment system was described in the 2014-2015 annual report and a telephone conversation (December 26, 2014) and email correspondence (January 26, 2016) between Rachelle Thompson of EPA and Scott Bourne, formerly of Weiss Associates.

<sup>4</sup> Design criteria for flow-based treatment established in IGP (SWRCB, 2014).

## 3 OPERATION AND MAINTENANCE

### 3.1 Upland Cap Maintenance

During the 2016-2017 reporting year, LRTC monitored the performance of concrete cap and gravel cover in accordance with recommendations contained in the 2015-2016 Annual Report (CDIM, 2016a). Deteriorating concrete identified in the southern portion of the eastern swale of the Main Terminal was observed to remain intact (Appendix A; Photo 12). LRTC continuously monitored other cracks, seals, and joints for signs of propagation and/or degradation. No evidence of exposed underlying soil was observed. The upland cap functioned as designed and no major maintenance or repair of the cap was conducted during the current reported period.

LRTC continued two projects during the reporting period which involved the upland cap: 1) installation of a roadway across three railroad tracks in the northern portion of the upland cap area (Appendix A; Photos 17, 19); and 2) installation of new concrete and fencing along the western edge of the cap in an area previously covered by wood timbers (Appendix A; Photos 2, 4) (Figure 3). These construction activities were undertaken to widen the existing roadway and provide additional drainage control. Work was performed during dry-weather conditions and neither activity resulted in the disturbance of underlying soil.

### 3.2 Storm Water Collection System Inspection and Cleaning

LRTC inspected the storm drain inlets, interceptors and clarifier tanks prior to the rainy season, and monthly throughout the reporting year in per its Storm Water Pollution Prevention Plan (SWPPP; CDIM, 2016b). Storm water interceptors and clarifier tanks are cleaned before the start of the rainy season. Drain inlets and inlet filters are cleaned and replaced as-needed throughout the year. Accumulated material removed from the inlets, interceptors and clarifier tanks appeared to be bulk product, which LRTC returned to the bulk product piles.

### 3.3 Storm Water Monitoring

The objective of the storm water monitoring program is to verify the cap is effectively preventing erosion, reducing the potential for storm water contact with soils containing residual pesticides, and reducing the potential for release of residual pesticides to the Lauritzen Channel. This section describes storm water sampling, results, quality assurance/quality control procedures. It includes an assessment of results.

#### 3.3.1 Storm Water Sampling

During the 2016-2017 reporting year, LRTC sampled industrial storm water discharges in accordance with State Water Resources Control Board (SWRCB) Water Quality Order No. 2014-0057-DWQ, National Pollutant Discharge Elimination System (NPDES) General Permit No. CAS000001, *General Permit for Storm Water Discharges Associated with Industrial Activities* (IGP; SWRCB, 2014); the O&M Plan (PES, 1999a); and, a Consent Decree between San Francisco Baykeeper and the Levin Richmond Terminal Corporation (United States District Court, 2014). Storm water monitoring requirements are documented in LRTC's SWPPP.

Prior to 2015, LRTC collected samples from interceptors SW-3 through SW-7. Since installing advanced treatment system TS-2, LRTC no longer regularly discharges storm water at these locations. As a result, LRTC

now collects storm water samples from the TS-2 influent and effluent.<sup>5</sup> In the event that elevated pesticides are detected in the TS-2 influent or effluent, LRTC is prepared to sample at interceptors SW-3 through SW-7.

The O&M Plan specifies that storm water samples be analyzed using EPA Method 8080. In previous years, storm water samples were analyzed for Method 8080 analytes using standard and low-level EPA Method 8081A to achieve lower method detection limits. In the fourth five-year review, the EPA recommended that analytical methods with detection limits lower than the marine surface water cleanup levels be used to allow for more meaningful evaluation of analytical data (EPA, 2016a). In an October 5, 2016 email from EPA, it was requested that samples from TS-2 be analyzed using EPA Method 1699 to achieve ultra-low detection limits (EPA, 2016b).

Storm water samples were submitted to Vista Analytical in El Dorado Hills, California for pesticide analysis by EPA Method 1699. Storm water samples were also submitted to Curtis & Tompkins in Berkeley, California and Eurofins CalScience Environmental Laboratories in Concord, California for the following analyses: pH by EPA Method 9040C, total suspended solids (TSS) by Standard Method 2540D, oil and grease (O&G) by EPA 1644A, and metals by EPA Method 200.7/200.8. Original laboratory reports, including applicable chain-of-custody forms, are included in Appendix B.<sup>6</sup>

### 3.3.2 Sample Results

During the 2016-2017 reporting year, storm water from the combined TS-2 influent and effluent was sampled during four storm events: October 14, 2016; December 8, 2016; January 3, 2017; and, January 18, 2017. The October 14, 2016 sampling event occurred during the first storm event (1.29 total inches of rainfall)<sup>7</sup> producing discharge for the 2016-2017 rainy season; its results represent the year's first flush.

#### 3.3.2.1 Effluent Sample Results

Tables 1 and 2 show laboratory analytical results for pesticides and general parameters/metals, respectively. Pesticides were detected in the treated storm water discharge samples (TS2-E) from each of the four sampling events during the 2016-2017 reporting year. Total DDT<sup>8</sup> was detected at concentrations ranging from 2,063 to 2,457 picograms per liter (pg/L); dieldrin was detected at concentrations from 1,300 to 2,770 pg/L.

Iron was detected in the January 3, 2017 TS-2 discharge sample above the IGP numeric action level (NAL) of 1,000 micrograms per liter (µg/L). TS-2 discharge results for all other pollutants (metals, O&G pH and TSS) were below the NALs during the 2016-2017 reporting year.

---

<sup>5</sup> Changes to storm water monitoring were discussed during a telephone conversation on November 3, 2015 between Rachelle Thompson of EPA and Scott Bourne of Weiss Associates.

<sup>6</sup> Laboratory analytical reports include data for storm water discharge points at LRT other than the upland cap area (TS1-E, TS3-E, TS4-E).

<sup>7</sup> Rainfall data from LRTC rain gauge.

<sup>8</sup> Total DDT represents the sum of detected concentrations of the 4,4' and 2,4'- isomers of DDT, DDD, and DDE and/or detection limits for non-detected compounds.



### 3.3.2.2 Influent Sample Results

Samples of the combined influent to TS-2 (TS2-I) were collected during each of the four events. Influent samples were composited using the SW-3, SW-4, and the combined SW-5/6/7 influent feeds; volume from each feed was calculated based on estimated runoff contribution to TS-2 discharge. Total DDT was detected at concentrations ranging from 35,469 to 147,040 pg/L; dieldrin was detected at concentrations from 3,190 to 7,310 pg/L.

### 3.3.3 Quality Assurance/Quality Control

The O&M Plan stipulates that at least one duplicate sample be collected for analysis by EPA Method 8080 per storm sampling event. However, due to the change to EPA Method 1699, it was determined that a duplicate pesticide sample was no longer necessary. EPA Method 1699 employs high-resolution gas chromatography/high-resolution mass spectrometry with isotope dilution and internal standard quantification techniques to provide improved sensitivity and data quality. In future years, a duplicate sample can be collected upon EPA request. A duplicate sample for general parameters and metals was collected during the January 18, 2017 event.

Laboratory method detection limits (MDLs) for each DDT isomer, and the sum of the MDLs for all DDT isomers, were below the total DDT final surface water remediation level of 590 pg/L established in the ROD (EPA, 1994b) for all events. The MDLs for dieldrin were below the final surface water remediation level of 140 pg/L.

No data quality issues were reported through the data validation process. Based on the data validation process, the data resulting from sampling and analysis are acceptable and complete.

### 3.3.4 Assessment of Results

Pesticides were detected in all TS-2 influent and effluent samples during the 2016-2017 reporting year. The implementation of EPA Method 1699 significantly reduced detection limits for all DDT isomers, resulting in an increased number of detections and more precise data. Using EPA Method 8081A, the sum of the detection limits for all DDT isomers was 3,500 pg/L. In 2016-2017, the total detected DDT concentration was below the previous detection limit, with concentrations ranging from 2,063 to 2,457 pg/L. Influent concentrations from 2016-2017 were higher than influent concentrations from 2015-2016, but were generally consistent with historical effluent data from interceptors SW-3 to SW-7 prior to implementation of TS-2.

Sample results from the 2016-2017 reporting year show that TS-2 is effective at reducing concentrations of Total DDT, TSS and metals.

Figure 4 presents the trend chart for influent and effluent DDT<sup>9</sup> concentrations from October 2015 to present. It provides both detected concentrations and non-detect results.<sup>10</sup> Prior to the 2015-2016 reporting year, storm water discharged from the upland area via individual interceptors. Concentration trend charts for DDT and dieldrin for individual storm water discharge locations from 2011 to 2015 are contained in the 2014-2015 Annual Report (Weiss, 2015a).

<sup>9</sup> Note that plotted DDT values are for the sum of the 4,4'- and 2,4'- isomers of DDT, DDD, and DDE.

<sup>10</sup> Denoted by "<n", where n is the sum of the DDT, DDD, and DDE detection limits, if available, or reporting limit otherwise.

### 3.4 Storm Water Treatment System Operation

LRT received approximately 37 inches of rainfall<sup>11</sup> during the 2016-2017 reporting period. LRTC reports that TS-2 provided sufficient treatment capacity to prevent treatment system bypass for all periods where its operation was observed. No significant operation and maintenance concerns were encountered. Sample results show that TS-2 is effective at reducing effluent TSS and pesticide concentrations.

---

<sup>11</sup> Rainfall from LRTC rain gauge.

## 4 ANNUAL SITE INSPECTION

Representatives of LRTC and CDIM inspected the upland cap on June 8, 2017. The inspection included visual observations of the concrete cap, gravel cover, and drainage system throughout the observable extent of the upland cap area. During a separate site visit on July 11, 2017, the cap in the bulk product storage area was inspected. Appendix A includes photographs taken during the inspections. Figure 3 shows the locations of photographs. Appendix C includes the inspection form.

### 4.1 Concrete Cap Inspection

Visual inspections concentrated on identifying signs of deterioration and exposure of the underlying subgrade at cracks, joints, high-loading areas, gravel and cap penetrations. Areas identified in the Third Five-Year Review (EPA, 2011) and the 2015-2016 Annual Report (CDIM, 2016a) with cracks and potential settlement were reexamined.

- **SW-3 Area** – Minor surficial cracks were observed to the west of the bulk product area, with some heavier cracks and seams south of interceptor SW-4 (Appendix A; Photos 1, 3). In the bulk product storage area, surficial cracks and seams were seen throughout (Appendix A; Photos 29, 30, and 31). Inspection of the northern end of the bulk product storage area was limited due to residual bulk material that obscured the cap surface (Appendix A; Photo 32). Additional concrete placed during the 2016-2017 reporting year was observed along the western edge of the SW-3 area (Appendix A; Photos 2 and 4).
- **SW-4 Area** – Areas of minor surficial cracks were observed throughout the SW-4 area. Cracks and seams were noted extending from the southeast corner of interceptor SW-4 toward the east and surrounding drain inlet 4DI-19 (Appendix A; Photos 5, 6, 9, and 10). Additional concrete placed along the western edge of SW-4 during the 2016-2017 reporting year was also observed (Appendix A; Photos 2, 4).
- **SW-5 Area** – Minor cracks were noted surrounding interceptor SW-5 and treatment system TS-2. Small areas of concrete deterioration were observed in the southern portion of the eastern swale of the Main Terminal; no change noted from previous year's inspection (Appendix A; Photo 12).
- **SW-6 Area** – Minor cracks were noted north and northeast of interceptor SW-6 (Appendix A; Photo 26), east of the rail tracks (Appendix A; Photos 20, 21, and 22), and along the eastern swale of the Main Terminal (Appendix A; Photos 27 and 28). Additional construction of the new road was observed (Appendix A; Photos 17 and 19).
- **SW-7 Area** – Minor surficial cracks were observed in this area (Photo 25).

No evidence of differential settling or vertical displacement was observed. No evidence of cracks, gaps, significant cap deterioration, or other material breach with apparent potential for exposure of the underlying subgrade was observed during the inspection. CDIM recommends that LRTC continue to monitor cracks and deterioration noted during the inspection. No repairs are required at this time.

### 4.2 Gravel Cover Inspection

Visual observations of the gravel cover concentrated on identifying areas where gravel cover was thin. A geotextile membrane underlies the gravel cover, but was not visually observed in any of the areas inspected. Below is a summary of observations from the concrete cap inspection.

- **SW-4 Area** – Some gravel cover has been replaced with concrete along the western edge of the area (Appendix A; Photos 2, 4).
- **SW-5 Area** – The gravel cover appeared adequate; the underlying geotextile fabric was not exposed in any area (Appendix A; Photos 11, 13, 14, 15, and 16).
- **SW-6 Area** – The gravel cover appeared adequate; the underlying geotextile fabric was not exposed in any area (Appendix A; Photo 23).

No visual evidence of differential settling or vertical displacement was observed. Overall, the gravel cover was found to be in good condition and functioning properly with no apparent potential for exposure of the underlying subgrade. CDIM recommends that LRTC continue to regularly inspect the gravel cover and perform maintenance as detailed in Section 6.

#### 4.1 Triennial Upland Cap Survey

In its Third-Five Year Review, the EPA recommended that the upland cap be periodically surveyed to monitor for differential settlement that could impact cap integrity (EPA, 2011). The baseline triennial survey was completed in May 2014 and included in the 2013-2014 Annual Report (Weiss, 2014).

Dillon & Murphy of Lodi, California performed the second triennial survey on May 9, 2017. The survey plat provided in Appendix D presents the 2017 point elevations and the baseline elevations for comparison. Elevations were within 0.01 inches at all survey locations, indicating no differential settlement has occurred in the previous three years. Triennial surveys will remain a part of the Site O&M program, with the next survey to occur during the 2019-2020 reporting period.

## 5 PROPOSED SITE WORK FOR 2017-2018

During the 2017-2018 reporting year, O&M activities will continue as follows:

- Storm water discharge samples will be collected from the TS-2 treatment system effluent (combined SW-3 through SW-7) discharge location. TS-2 influent samples will also be collected to evaluate system effectiveness.
- An annual inspection of the concrete cap and gravel cover in the upland cap area will be performed in the early summer of 2018.
- Regular inspections of the upland capping system, including the drainage system, will continue as part of the SWPPP (CDIM, 2016b) compliance activities and daily operations.
- As needed, filling of significant cracks and replacement of deteriorated sections of concrete in the upland capping system.

Proposed site work under the O&M Plan for 2017-2018 is presented in Table 3.

Any repairs to the cap, if required, will be documented and reported in a memorandum to the EPA and the California Department of Toxic Substances Control.

## 6 CONCLUSIONS AND RECOMMENDATIONS

The annual upland capping system inspection found that the surface cap is in overall good condition and effectively functions to prevent erosion of the underlying soil. Storm water sampling results from the upland cap area indicate that treatment system TS-2 is effective in reducing the discharge of pesticides.

CDIM recommends continuing the following maintenance and monitoring activities:

- Monitor gravel cover areas of SW-5 and SW-6;
- Monitor deteriorated concrete in the southern portion of the eastern swale of the Main Terminal at SW-5.
- As needed, fill significant cracks and replace deteriorated sections of concrete in the upland capping system;
- Implement regular inspections and BMPs identified in the LRT SWPPP (CDIM, 2016b); and,
- Continue to monitor storm water for pesticides as described herein.

## 7 REFERENCES

CDIM Engineering (CDIM), 2016a. 2015-2016 Annual Report for United Heckathorn Superfund Site, Upland Capping System, Richmond, California, August 30.

\_\_\_\_\_, 2016b. Storm Water Pollution Prevention Plan, Levin Richmond Terminal, 402 Wright Avenue, Richmond, California, September.

CH2MHill, 2012. Summary of Field Activities to Support Phase 4 Source Identification Study United Heckathorn Superfund Site, Richmond, California. January 3.

PES Environmental, Inc. (PES), 1998. Pre-Final/Final Design and Remedial Action Work Plan, Former United Heckathorn Site, Upland Capping Project, Richmond, California. April 7.

\_\_\_\_\_, 1999a. Revised Draft Operations and Maintenance Plan, Upland Capping System, Former United Heckathorn Site, March.

\_\_\_\_\_, 1999b. Report Requesting Certification of Completion of Upland Cap Installation, Former United Heckathorn Facility. September 16.

State Water Resources Control Board, 2014. General Permit for Storm Water Discharges Associated with Industrial Activities, Order No. 2014-0057-DWQ, National Pollutant Discharge Elimination System General Permit No. CAS000001, April.

United States District Court, Northern District of California, 1996a. Consent Decree, Levin Group RD/RA, United States of America Plaintiff v. Montrose Chemical Corporation of California, et al., June.

\_\_\_\_\_, 1996b. Consent Decree, Montrose Group RD/RA, United States of America Plaintiff v. Montrose Chemical Corporation of California, et al., July 19.

\_\_\_\_\_, Northern District of California, 2014. Consent Decree, San Francisco Baykeeper v. Levin Enterprises, et al., August.

United States Environmental Protection Agency (EPA), 1994a. Feasibility Study for the United Heckathorn Superfund Site, Richmond, California. July.

\_\_\_\_\_, 1994b. EPA Superfund Record of Decision: United Heckathorn Co., EPA ID: CAD981436363; OU 01, Richmond, CA, EPA/ROD/R09-96/5021996, October.

\_\_\_\_\_, 2011. Third Five-Year Review Report for United Heckathorn Superfund Site, Richmond, California, September.

\_\_\_\_\_, 2016a. Fourth Five-Year Review Report for United Heckathorn Superfund Site, Richmond, California, August.

\_\_\_\_\_, 2016b. Email from Karen Jurist of EPA to Scott Bourne of CDIM Engineering, October 5.

Weiss Associates, 2014. 2013-2014 Annual Report for the United Heckathorn Superfund Site, Upland Capping System, Richmond, California, July 15.

\_\_\_\_\_, 2015a. 2014-2015 Annual Report for the United Heckathorn Superfund Site, Upland Capping System, Richmond, California, September 11.



## **TABLES**



Table 1. 2016-2017 Storm Water Sample Analytical, Pesticides, Levin Richmond Terminal Corporation

Discharge Location	Notes	Analytical results <sup>a</sup>																												
		2,4'-DDD pg/L	4,4'-DDD pg/L	2,4'-DDE pg/L	4,4'-DDE pg/L	2,4'-DDT pg/L	4,4'-DDT pg/L	Total DDT pg/L	Aldrin pg/L	alpha-BHC pg/L	alpha-Chlordane pg/L	beta-BHC pg/L	cis-Nonachlor pg/L	delta-BHC pg/L	Dieldrin pg/L	Endosulfan I pg/L	Endosulfan II pg/L	Endosulfan sulfate pg/L	Endrin pg/L	Endrin aldehyde pg/L	Endrin ketone pg/L	gamma-BHC (Lindane) pg/L	gamma-Chlordane pg/L	Heptachlor pg/L	Heptachlor epoxide <sup>d</sup> pg/L	Hexachlorobenzene pg/L	Methoxychlor pg/L	Mirex pg/L	Oxychlordane pg/L	trans-Nonachlor pg/L
INFLUENT																														
TS2-I <sup>b</sup>																														
10/14/2016		3,250	7,130	699	8,720	3,070	12,600	35,469	<29.1	93.7 J	802	<57.5	<226	<38.5	3,960 B	<141	<332	<740	1,070	<1,050	<16,200**	90.3	875	167 J	96.0 J	1,310 B	<7,620	<136	<93.3	345 J
12/8/2016		8,960	19,400 D	1,610 D	20,000 D	18,900 D	61,800 D	130,670 D	65.1	89.3*	4,380	<93.2**	511	<23.6	7,310 D	<127	<552	<694	1,440	<857*	<561	111	2,970	<90.0**	254	2,650 B	<542	<111	<87.0	1,730
1/3/2017		5,440	13,100	730	8,930	9,290	34,400 D	71,890 D	<30.6**	75.6	2,920	66.6	<192**	<9.02	3,190	<27.8	<147	<95.6	780	<65.7	<151	92.0	1,620	42.8	961	292	<364	<11.2	69.8	921
1/18/2017		11,800	25,400 D	2,040	22,400	20,600	64,800 D	147,040 D	77.4	68.2	2,520	82.6	<200**	<12.6	3,810	<47.8	<273 D	<407 D	1,100	<581 D	<624 D	89.8	1,640	67.0	186	800	<477	<59.4	<34.3	983
EFFLUENT																														
TS2-E <sup>c</sup>																														
10/14/2016		300 J	485	46.5 J	471	175 J	585	2,063	<37.9	<54.3**	201 J	153 J	<194	<28.5	1,640 B	<120	<336	<646	531	<337	<506	<35.1	<102	<32.8	<258	120 J,B	<736	<48.7	<102	<97.6
12/8/2016		194	410	25.5 J*	381*	233	951	2,195	<5.55	75.5	<134**	69.2	<52.0*	<5.59	1,460	<42.7	<168	<306	470	<220	726	86.8	<72.8**	<9.54	181.9	67.1 B	<241	<30.9	<23.8	58.3
1/3/2017		378	770	27.6 J	207	307	767	2,457	<3.83	41.4	223	57.8	<10.1	<5.38	1,300	<15.6	<40.5	<23.6	356	<12.8	433	88.1	<87.6**	<11.1	804	27.9 J	<32.5	<2.36	<18.3	54.3
1/18/2017		409	700	24.2 J	191	266	619	2,209	<5.49	52.5	378	191	<22.8	<2.89	2,770	<21.0	<80.4	<118	769	<47.5	1,960	48.8	132	<2.02	1,007	29.1	<16.1	<12.0	<15.3	60.4
Remediation Goal <sup>e</sup>		590														140														

**Notes:**  
Detected concentrations of pesticides are displayed in **bold**.  
\* Laboratory surrogate recoveries for this analyte outside of quality control standards due to matrix interference; result may be biased.  
\*\* Not detected; reported value is estimated maximum possible concentration.  
<sup>a</sup> Laboratory method EPA 1699.  
<sup>b</sup> TS2-I is the combined influent from interceptors SW-3 to SW-7 and does not represent discharge. It is used to evaluate TS-2 effectiveness.  
<sup>c</sup> TS2-E is the effluent of treatment system TS-2, which treats storm water from interceptors SW-3 to SW-7. It represents facility discharge.  
<sup>d</sup> Reported result is sum of detected cis- and trans-heptachlor epoxide concentrations.  
<sup>e</sup> Remediation goal from USEPA Superfund Record of Decision: United Heckathorn Co., October 1994, for surface waters in the Lauritzen, Santa Fe, and lower Richmond Inner Harbor Channels.

**Acronyms/Abbreviations:**

--- = not analyzed

B = compound was also detected in laboratory method blank

D = sample diluted for analysis; concentration calculated value

J = concentration reported is an estimated value

< *n* =not detected above the sample-specific estimated detection limit

pg/L = picograms per liter

USEPA = United States Environmental Protection Agency

Table 2. 2016-2017 Storm Water Sample Analytical Results, General Parameters and Metals, Levin Richmond Terminal Corporation

Discharge Location	Notes	Analytical Parameters <sup>a</sup>							
		pH	O&G (HEM)	TSS	Aluminum	Copper	Iron	Lead	Zinc
		-	mg/L	mg/L	µg/L	µg/L	µg/L	µg/L	µg/L
<b>INFLUENT</b>									
<b>TS2-I<sup>b</sup></b>									
10/14/2016		8.0	1.9 J	160	703	20.5	1,260	18.4	432
12/8/2016		6.95	2.1	175	584	21.5	2,070	72.9	255
1/3/2017		7.90	<1.0	27	293	10.9	1,050	9.12	169
1/18/2017		7.76	1.0	131	721	13.5	1,870	89.8	250 B
<b>EFFLUENT</b>									
<b>TS2-E<sup>c</sup></b>									
10/14/2016		8.0	<5.26	10	57 J	7.8	<100	<5.0	47
12/8/2016		7.37	<1.0	3.8	19.5 J	12.2	74.9	4.05	118
1/3/2017		8.04	<1.0	1.4	16.4 J	13.4	<b>1,800 / 1,620<sup>d</sup></b>	5.34	119
1/18/2017		7.55	<1.0	1.7	13.3 J	3.11	25.3 J	2.14	114 B
1/18/2017	Duplicate	7.86	<1.0	<1.0	14.6 J	3.39	26.2 J	2.29	115 B
<b>2014 IGP Numeric Action Levels (NALs)<sup>e</sup></b>		6.0-9.0 <sup>f</sup>	15	100	750	33.2	1,000	262	260

**Notes:**

**Bold** values exceed 2014 IGP NALs listed at the bottom of the table.

<sup>a</sup> Laboratory Methods: pH by EPA 9040C; TSS by SM2540D, O&G by EPA 1664A; metals by EPA 200.7/200.8.

<sup>b</sup> TS2-I is the combined influent from interceptors SW-3 to SW-7 and does not represent discharge. It is used to evaluate TS-2 effectiveness.

<sup>c</sup> TS2-E is the effluent of treatment system TS-2, which treats storm water from interceptors SW-3 to SW-7.

<sup>d</sup> Sample was re-analyzed due to unexpected result in original lab report.

**Acronyms/Abbreviations:**

B = compounds was found in blank and sample

J = concentration reported is an estimated value

mg/L = milligrams per liter

< n = not detected above the reporting limit

O&G (HEM) = oil and grease hexane extractable

TSS = total suspended solids


Table 3. Proposed Site Work for 2017-2018, Levin Richmond Terminal Corporation

Aspect	Description	Anticipated Completion Date
General	Implement activities (i.e., cap maintenance, storm water monitoring, interceptor cleanout) described in the O&M Plan. <sup>1</sup>	Continuously
	Submit report of O&M performed for the period of July 1, 2017 to June 30, 2018.	On/around August 15, 2018
Concrete Cap	Perform 2017-2018 annual inspection of the cap under oversight of a registered engineer.	June 1, 2018
	Monitor deteriorated concrete in the southern portion of the eastern swale of the Main Terminal identified in Photos 18 and 19 (Appendix A); replace affected sections should evidence of underlying soil be observed.	Continuously
	Monitor identified cracks, seals, and joints for signs of propagation and/or degradation throughout upland capping system.	Continuously
Gravel Cover	Monitor the gravel cover throughout the Upland Area for signs of thinning or ground exposure.	Continuously
Storm Water System	Continue to treat combined storm water pumped from interceptors SW-3, SW-4, SW-5, SW-6, and SW-7 at treatment system TS-2 using flocculation, settling, and filtration methods.	Continuously


<sup>1</sup> Revised Draft Operations and Maintenance Plan, Upland Capping System, Former United Heckathorn Site, PES Environmental, Inc., March 1999.

## FIGURES
















CDIM ENGINEERING, INC.  
45 POLK STREET, THIRD FLOOR  
SAN FRANCISCO, CA 94102  
WWW.CDIMENGINEERING.COM  
PH: (415) 498-0535

UPLAND CAPPING SYSTEM DETAILS  
UNITED HECKATHORN SUPERFUND SITE  
RICHMOND, CALIFORNIA

FIGURE  
3





NOTE: Total DDT represents the sum of detected DDT, DDD, and DDE concentrations and/or detection limits for non-detected compounds (denoted by < n).

## **APPENDIX A**

### Upland Capping System Inspection Photos




Photo 1 – Looking north along western alley of secondary storage area: new curbing and wind fence added to 2015-2016 concrete work to widen road.




Photo 2 – Closeup view of new curbing and wind fence.






Photo 3 – Looking north toward interceptor SW-4: seams and areas of surficial cracking. No change noted from previous year.




Photo 4 - Looking south: new concrete work completed during 2016-2017 reporting year.





Photo 5 – Looking east from corner of interceptor SW-4: crack extending east with sealant and concrete wearing at seams. No change noted from previous year.



Photo 6 – Looking east: concrete seams and surficial cracks.





Photo 7 - Looking north: shoreline shotcrete placed in 2015-2016 reporting year.




Photo 8 - Looking north: gravel cover to the west of new asphalt pavement south of treatment system TS-2 and interceptor SW-5.





Photo 9 – Looking east: surficial cracking east of interceptor SW-4.



Photo 10 – Looking north: seams and surficial cracking along rail line.





Photo 11 – Looking south: gravel cover along eastern perimeter.



Photo 12 – Looking north: areas of minor concrete deterioration at the southern portion of the eastern swale. No change from previous year.






Photo 13 – Looking northeast: gravel cover along rail lines.



Photo 14 – Looking north: gravel cover along rail lines.





Photo 15 – Looking south: gravel cover between rail lines with some areas of thinning.



Photo 16 – Looking north: gravel cover with some thinning areas to the east of diesel fuel tank.





Photo 17 – Looking northeast: new asphalt across rail lines installed in 2016-2017 replaced existing gravel cover.



Photo 18 – Looking north: gravel cover north of new road.





Photo 19 – Looking south: new road (installed 2015-2016) and asphalt (installed 2016-2017).




Photo 20 – Looking southeast: concrete seams with new asphalt in background.





Photo 21 – Looking east: surficial cracks east of rail lines.



Photo 22 – Looking north: cap area south of interceptor SW-6.





Photo 23 – Looking northeast toward northern gate: gravel cover area.




Photo 24 – Looking west toward municipal outfall: shotcrete along northern shoreline.





Photo 25 – Looking west: seams and surficial cracks east of interceptor SW-7.



Photo 26 – Looking east: seams and surficial cracks northeast of interceptor SW-6.






Photo 27 – Looking south: seams and surficial cracks in swale on eastern perimeter of site.




Photo 28 – Looking south: seams gravel cover in railroad maintenance area.





Photo 29 – Looking north: surficial cracks at southern end of bulk product storage area.



Photo 30 – Looking north: seam running north to south in bulk product storage area.





Photo 31 – Looking west: surficial cracking within bulk product storage area.



Photo 32 – Looking north: residual bulk product pile obscuring cap surface.

## **APPENDIX B**

### Laboratory Analytical Reports



November 09, 2016

**Vista Work Order No. 1601325**

Mr. Scott Bourne  
CDIM Engineering  
45 Polk Street, 3rd Floor  
San Francisco, CA 94102

Dear Mr. Bourne,

Enclosed are the results for the sample set received at Vista Analytical Laboratory on October 18, 2016. This sample set was analyzed on a standard turn-around time, under your Project Name '101-001-LRTC, Task 1'.

Vista Analytical Laboratory is committed to serving you effectively. If you require additional information, please contact me at 916-673-1520 or by email at [mmaier@vista-analytical.com](mailto:mmaier@vista-analytical.com).

Thank you for choosing Vista as part of your analytical support team.

Sincerely,

Martha Maier  
Laboratory Director



*Vista Analytical Laboratory certifies that the report herein meets all the requirements set forth by NELAP for those applicable test methods. Results relate only to the samples as received by the laboratory. This report should not be reproduced except in full without the written approval of Vista.*

## Vista Work Order No. 1601325

### Case Narrative

#### Sample Condition on Receipt:

Two water samples were received in good condition and within the method temperature requirements. The samples were received and stored securely in accordance with Vista standard operating procedures and EPA methodology.

#### Analytical Notes:

#### EPA Method 1699

These samples were extracted and analyzed for chlorinated pesticides by EPA Method 1699 using a ZB-50 GC column.

#### Holding Times

The samples were extracted and analyzed within the method hold times.

#### Quality Control

The Initial Calibration and Continuing Calibration Verifications met the method acceptance criteria.

A Method Blank and Ongoing Precision and Recovery (OPR) sample were extracted and analyzed with the preparation batch. No analytes were detected above the sample quantitation limits in the Method Blank. The recovery of Endrin Aldehyde was 179% in the OPR; this analyte was not detected in either of the field samples. The OPR recoveries were within the method acceptance criteria for all other analytes.

The labeled standard recoveries outside the method acceptance criteria are listed in the table below.

#### QC Anomalies

LabNumber	SampleName	Analysis	Analyte	Flag	%Rec
1601325-01	TS2-I-161014	EPA Method 1699	13C12-Aldrin	H	123
1601325-02	TS2-E-161014	EPA Method 1699	13C10-cis-Heptachlor Epoxide	H	151

H = Recovery was outside laboratory acceptance criteria.

## TABLE OF CONTENTS

Case Narrative.....	1
Table of Contents.....	3
Sample Inventory.....	4
Analytical Results.....	5
Qualifiers.....	10
Certifications.....	11
Sample Receipt.....	14

# Sample Inventory Report

Vista Sample ID	Client Sample ID	Sampled	Received	Components/Containers
1601325-01	TS2-I-161014	14-Oct-16 14:20	18-Oct-16 08:58	Amber Glass NM Bottle, 1L Amber Glass NM Bottle, 1L Amber Glass NM Bottle, 1L
1601325-02	TS2-E-161014	14-Oct-16 14:40	18-Oct-16 08:58	Amber Glass NM Bottle, 1L Amber Glass NM Bottle, 1L Amber Glass NM Bottle, 1L

## **ANALYTICAL RESULTS**



Sample ID: Method Blank					EPA Method 1699				
Matrix: Aqueous		QC Batch: B6J0134			Lab Sample: B6J0134-BLK1				
Sample Size: 0.100 L		Date Extracted: 21-Oct-2016 13:56			Date Analyzed: 03-Nov-16 00:45 Column: ZB-50				
Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers	
Hexachlorobenzene	51.6			J	IS 13C6-Hexachlorobenzene	47.7	5 - 120		
alpha-BHC	ND	30.7			IS 13C6-alpha-BHC	55.8	32 - 130		
Lindane (gamma-BHC)	ND	36.9			IS 13C6-Lindane (gamma-BHC)	70.7	11 - 120		
beta-BHC	ND	33.9			IS 13C6-beta-BHC	80.1	32 - 130		
delta-BHC	ND	23.9			IS 13C6-delta-BHC	84.9	36 - 137		
Heptachlor	ND	8.04			IS 13C10-Heptachlor	68.8	5 - 120		
Aldrin	ND	16.0			IS 13C12-Aldrin	74.8	5 - 120		
Oxychlordane	ND	37.9			IS 13C10-Oxychlordane	87.3	23 - 135		
cis-Heptachlor Epoxide	ND	27.4			IS 13C10-cis-Heptachlor Epoxide	112	27 - 137		
trans-Heptachlor Epoxide	ND	69.4			IS 13C10-trans-Chlordane (gamma)	91.7	21 - 132		
trans-Chlordane (gamma)	ND	36.8			IS 13C10-trans-Nonachlor	94.8	14 - 136		
trans-Nonachlor	ND	33.1			IS 13C9-Endosulfan I (alpha)	102	15 - 148		
cis-Chlordane (alpha)	ND	31.8			IS 13C12-2,4'-DDE	102	47 - 160		
Endosulfan I (alpha)	ND		83.8		IS 13C12-4,4'-DDE	106	47 - 160		
2,4'-DDE	ND	30.5			IS 13C12-Dieldrin	96.8	40 - 151		
4,4'-DDE	ND	31.9			IS 13C12-Endrin	116	35 - 155		
Dieldrin	89.5			J	IS 13C10-cis-Nonachlor	96.9	36 - 139		
Endrin	ND	23.8			IS 13C9-Endosulfan II (beta)	93.9	5 - 122		
cis-Nonachlor	ND	30.8			IS 13C12-2,4'-DDD	106	5 - 199		
Endosulfan II (beta)	ND	47.2			IS 13C12-2,4'-DDT	112	5 - 199		
2,4'-DDD	ND	42.5			IS 13C12-4,4'-DDD	104	5 - 120		
2,4'-DDT	ND	65.1			IS 13C12-4,4'-DDT	112	5 - 120		
4,4'-DDD	ND	50.2			IS 13C9-Endosulfan Sulfate	93.6	15 - 148		
4,4'-DDT	ND	73.9			IS 13C12-Methoxychlor	99.1	5 - 120		
Endosulfan Sulfate	ND	49.0			IS 13C10-Mirex	76.3	5 - 120		
4,4'-Methoxychlor	ND	32.7			IS 13C12-Endrin Aldehyde	64.1	15 - 148		
Mirex	ND	6.86			IS 13C12-Endrin Ketone	99.1	15 - 148		
Endrin Aldehyde	ND	39.9							
Endrin Ketone	ND	38.8							

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Sample ID: OPR

EPA Method 1699

Matrix: Aqueous  
Sample Size: 0.100 LQC Batch: B6J0134  
Date Extracted: 21-Oct-2016 13:56Lab Sample: B6J0134-BS1  
Date Analyzed: 02-Nov-16 22:17 Column: ZB-50

Analyte	Amt Found (pg/L)	Spike Amt	%R	Limits	Labeled Standard	%R	LCL-UCL
Hexachlorobenzene	10100	10000	101	50 - 120	IS 13C6-Hexachlorobenzene	70.5	5 - 120
alpha-BHC	9350	10000	93.5	50 - 120	IS 13C6-alpha-BHC	80.8	17 - 141
Lindane (gamma-BHC)	9030	10000	90.3	50 - 120	IS 13C6-Lindane (gamma-BHC)	85.3	5 - 124
beta-BHC	9080	10000	90.8	50 - 120	IS 13C6-beta-BHC	83.5	17 - 141
delta-BHC	7900	10000	79.0	50 - 120	IS 13C6-delta-BHC	88.8	16 - 150
Heptachlor	9150	10000	91.5	50 - 120	IS 13C10-Heptachlor	89.0	5 - 128
Aldrin	9410	10000	94.1	50 - 120	IS 13C12-Aldrin	78.2	5 - 126
Oxychlordane	9670	10000	96.7	50 - 120	IS 13C10-Oxychlordane	91.3	5 - 144
cis-Heptachlor Epoxide	9000	10000	90.0	50 - 120	IS 13C10-cis-Heptachlor Epoxide	97.8	8 - 146
trans-Heptachlor Epoxide	8750	10000	87.5	50 - 120	IS 13C10-trans-Chlordane (gamma)	89.4	15 - 144
trans-Chlordane (gamma)	9260	10000	92.6	50 - 120	IS 13C10-trans-Nonachlor	86.2	13 - 149
trans-Nonachlor	9980	10000	99.8	50 - 120	IS 13C9-Endosulfan I (alpha)	80.6	5 - 144
cis-Chlordane (alpha)	10300	10000	103	50 - 120	IS 13C12-2,4'-DDE	98.8	26 - 169
Endosulfan I (alpha)	9360	10000	93.6	50 - 120	IS 13C12-4,4'-DDE	102	26 - 169
2,4'-DDE	9590	10000	95.9	24 - 123	IS 13C12-Dieldrin	67.8	19 - 161
4,4'-DDE	8610	10000	86.1	50 - 120	IS 13C12-Endrin	66.0	20 - 157
Dieldrin	9700	10000	97.0	50 - 120	IS 13C10-cis-Nonachlor	90.0	17 - 154
Endrin	8930	10000	89.3	50 - 120	IS 13C9-Endosulfan II (beta)	31.4	5 - 120
cis-Nonachlor	10100	10000	101	50 - 120	IS 13C12-2,4'-DDD	102	14 - 200
Endosulfan II (beta)	10100	10000	101	5 - 200	IS 13C12-2,4'-DDT	109	14 - 200
2,4'-DDD	9580	10000	95.8	50 - 120	IS 13C12-4,4'-DDD	102	14 - 200
2,4'-DDT	9650	10000	96.5	50 - 120	IS 13C12-4,4'-DDT	109	13 - 200
4,4'-DDD	9210	10000	92.1	42 - 120	IS 13C9-Endosulfan Sulfate	27.9	5 - 144
4,4'-DDT	8990	10000	89.9	50 - 120	IS 13C12-Methoxychlor	52.2	8 - 200
Endosulfan Sulfate	9050	10000	90.5	50 - 120	IS 13C10-Mirex	78.9	5 - 138
4,4'-Methoxychlor	9200	10000	92.0	50 - 120	IS 13C12-Endrin Aldehyde	8.10	5 - 144
Mirex	9320	10000	93.2	50 - 120	IS 13C12-Endrin Ketone	19.4	5 - 144
Endrin Aldehyde	17900	10000	179	50 - 134			
Endrin Ketone	12000	10000	120	50 - 134			

LCL-UCL - Lower control limit - upper control limit

**Sample ID: TS2-I-161014**

**EPA Method 1699**

Client Data			Sample Data		Laboratory Data			
Name:	CDIM Engineering		Matrix:	Water	Lab Sample:	1601325-01	Date Received:	18-Oct-2016 8:58
Project:	101-001-LRTC, Task 1		Sample Size:	0.100 L	QC Batch:	B6J0134	Date Extracted:	21-Oct-2016 13:56
Date Collected:	14-Oct-2016 14:20				Date Analyzed:	03-Nov-16 10:42	Column:	ZB-50
Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Hexachlorobenzene	1310			B	IS 13C6-Hexachlorobenzene	79.4	5 - 120	
alpha-BHC	93.7			J	IS 13C6-alpha-BHC	78.1	32 - 130	
Lindane (gamma-BHC)	90.3			J	IS 13C6-Lindane (gamma-BHC)	84.2	11 - 120	
beta-BHC	ND	57.5			IS 13C6-beta-BHC	61.9	32 - 130	
delta-BHC	ND	38.5			IS 13C6-delta-BHC	70.5	36 - 137	
Heptachlor	167			J	IS 13C10-Heptachlor	81.6	5 - 120	
Aldrin	ND	29.1			IS 13C12-Aldrin	123	5 - 120	H
Oxychlordane	ND	93.3			IS 13C10-Oxychlordane	64.6	23 - 135	
cis-Heptachlor Epoxide	96.0			J	IS 13C10-cis-Heptachlor Epoxide	99.2	27 - 137	
trans-Heptachlor Epoxide	ND	208			IS 13C10-trans-Chlordane (gamma)	61.8	21 - 132	
trans-Chlordane (gamma)	875				IS 13C10-trans-Nonachlor	82.2	14 - 136	
trans-Nonachlor	345			J	IS 13C9-Endosulfan I (alpha)	104	15 - 148	
cis-Chlordane (alpha)	802				IS 13C12-2,4'-DDE	88.0	47 - 160	
Endosulfan I (alpha)	ND	141			IS 13C12-4,4'-DDE	77.2	47 - 160	
2,4'-DDE	699				IS 13C12-Dieldrin	68.5	40 - 151	
4,4'-DDE	8720				IS 13C12-Endrin	63.9	35 - 155	
Dieldrin	3960			B	IS 13C10-cis-Nonachlor	45.8	36 - 139	
Endrin	1070				IS 13C9-Endosulfan II (beta)	44.4	5 - 122	
cis-Nonachlor	ND	226			IS 13C12-2,4'-DDD	65.4	5 - 199	
Endosulfan II (beta)	ND	332			IS 13C12-2,4'-DDT	56.4	5 - 199	
2,4'-DDD	3250				IS 13C12-4,4'-DDD	49.4	5 - 120	
2,4'-DDT	3070				IS 13C12-4,4'-DDT	30.3	5 - 120	
4,4'-DDD	7130				IS 13C9-Endosulfan Sulfate	30.2	15 - 148	
4,4'-DDT	12600				IS 13C12-Methoxychlor	22.7	5 - 120	
Endosulfan Sulfate	ND	740			IS 13C10-Mirex	25.0	5 - 120	
4,4'-Methoxychlor	ND	7620			IS 13C12-Endrin Aldehyde	25.0	15 - 148	
Mirex	ND	136			IS 13C12-Endrin Ketone	24.6	15 - 148	
Endrin Aldehyde	ND	1050						
Endrin Ketone	ND		16200					

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Sample ID: TS2-E-161014

EPA Method 1699

Client Data			Sample Data		Laboratory Data			
Name:	CDIM Engineering		Matrix:	Water	Lab Sample:	1601325-02	Date Received:	18-Oct-2016 8:58
Project:	101-001-LRTC, Task 1		Sample Size:	0.100 L	QC Batch:	B6J0134	Date Extracted:	21-Oct-2016 13:56
Date Collected:	14-Oct-2016 14:40				Date Analyzed:	03-Nov-16 11:31	Column:	ZB-50
Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Hexachlorobenzene	120			J, B	IS 13C6-Hexachlorobenzene	66.1	5 - 120	
alpha-BHC	ND		54.3		IS 13C6-alpha-BHC	68.2	32 - 130	
Lindane (gamma-BHC)	ND	35.1			IS 13C6-Lindane (gamma-BHC)	79.4	11 - 120	
beta-BHC	153			J	IS 13C6-beta-BHC	90.4	32 - 130	
delta-BHC	ND	28.5			IS 13C6-delta-BHC	89.4	36 - 137	
Heptachlor	ND	32.8			IS 13C10-Heptachlor	67.2	5 - 120	
Aldrin	ND	37.9			IS 13C12-Aldrin	116	5 - 120	
Oxychlordane	ND	102			IS 13C10-Oxychlordane	60.5	23 - 135	
cis-Heptachlor Epoxide	ND	73.1			IS 13C10-cis-Heptachlor Epoxide	151	27 - 137	H
trans-Heptachlor Epoxide	ND	185			IS 13C10-trans-Chlordane (gamma)	115	21 - 132	
trans-Chlordane (gamma)	ND	102			IS 13C10-trans-Nonachlor	119	14 - 136	
trans-Nonachlor	ND	97.6			IS 13C9-Endosulfan I (alpha)	145	15 - 148	
cis-Chlordane (alpha)	201			J	IS 13C12-2,4'-DDE	132	47 - 160	
Endosulfan I (alpha)	ND	120			IS 13C12-4,4'-DDE	123	47 - 160	
2,4'-DDE	46.5			J	IS 13C12-Dieldrin	95.7	40 - 151	
4,4'-DDE	471				IS 13C12-Endrin	105	35 - 155	
Dieldrin	1640			B	IS 13C10-cis-Nonachlor	78.1	36 - 139	
Endrin	531				IS 13C9-Endosulfan II (beta)	82.5	5 - 122	
cis-Nonachlor	ND	194			IS 13C12-2,4'-DDD	101	5 - 199	
Endosulfan II (beta)	ND	336			IS 13C12-2,4'-DDT	85.0	5 - 199	
2,4'-DDD	300			J	IS 13C12-4,4'-DDD	85.8	5 - 120	
2,4'-DDT	175			J	IS 13C12-4,4'-DDT	62.8	5 - 120	
4,4'-DDD	485				IS 13C9-Endosulfan Sulfate	73.4	15 - 148	
4,4'-DDT	585				IS 13C12-Methoxychlor	39.6	5 - 120	
Endosulfan Sulfate	ND	646			IS 13C10-Mirex	44.8	5 - 120	
4,4'-Methoxychlor	ND	736			IS 13C12-Endrin Aldehyde	52.2	15 - 148	
Mirex	ND	48.7			IS 13C12-Endrin Ketone	53.3	15 - 148	
Endrin Aldehyde	ND	337						
Endrin Ketone	ND	506						

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

## **DATA QUALIFIERS & ABBREVIATIONS**

<b>B</b>	<b>This compound was also detected in the method blank.</b>
<b>D</b>	<b>Dilution</b>
<b>E</b>	<b>The associated compound concentration exceeded the calibration range of the instrument.</b>
<b>H</b>	<b>Recovery and/or RPD was outside laboratory acceptance limits.</b>
<b>I</b>	<b>Chemical Interference</b>
<b>J</b>	<b>The amount detected is below the Reporting Limit/LOQ.</b>
<b>*</b>	<b>See Cover Letter</b>
<b>Conc.</b>	<b>Concentration</b>
<b>NA</b>	<b>Not applicable</b>
<b>ND</b>	<b>Not Detected</b>
<b>TEQ</b>	<b>Toxic Equivalency</b>

**Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.**

## **CERTIFICATIONS**

<b>Accrediting Authority</b>	<b>Certificate Number</b>
California Department of Health – ELAP	2892
DoD ELAP - A2LA Accredited - ISO/IEC 17025:2005	3091.01
Florida Department of Health	E87777
Hawaii Department of Health	N/A
Louisiana Department of Environmental Quality	01977
Maine Department of Health	2014022
Nevada Division of Environmental Protection	CA004132015-1
New Jersey Department of Environmental Protection	CA003
New York Department of Health	11411
Oregon Laboratory Accreditation Program	4042-004
Pennsylvania Department of Environmental Protection	012
South Carolina Department of Health	87002001
Texas Commission on Environmental Quality	T104704189-15-6
Virginia Department of General Services	7923
Washington Department of Ecology	C584
Wisconsin Department of Natural Resources	998036160

*Current certificates and lists of licensed parameters are located in the Quality Assurance office and are available upon request*



## NELAP Accredited Test Methods

MATRIX: Air	
Description of Test	Method
Determination of Polychlorinated p-Dioxins & Polychlorinated Dibenzofurans	EPA 23

MATRIX: Biological Tissue	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Drinking Water	
Description of Test	Method
2,3,7,8-Tetrachlorodibenzo- p-dioxin (2,3,7,8-TCDD) GC/HRMS	EPA 1613
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537

MATRIX: Non-Potable Water	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Dioxin by GC/HRMS	EPA 613
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Solids	
Description of Test	Method
Tetra-Octa Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope	EPA 1613B

Dilution GC/HRMS	
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

**Vista Analytical**  
1104 Windfield Way  
El Dorado Hills, CA 95762  
Phone: (916) 673-1520

Please send analytic results, electronic deliverables and the original chain-of-custody form to:  
sab@cdimengineering.com  
mec@cdimengineering.com

GeoTracker EDF required?      ☐ Yes      ☒ No  
Equis 4-file EDWEDD required?      ☒ Yes      ☐ No  
Specify analytic/prep method and detection limit in report.  
Notify us of any anomalous peaks in GC or other scans.  
Call immediately with any questions or problems.

1601325

5.3°C

[illegible]

x = Samples released to a secured, locked area

● = Samples received from a secured, locked area

# SAMPLE LOG-IN CHECKLIST



Vista Project #: 1601325 TAT Std

Samples Arrival:	Date/Time 10/18/16 0858	Initials: UBB	Location: WR-2
Logged In:	Date/Time 10/18/16 1332	Initials: UBB	Location: WR-2 Shelf/Rack: B5
Delivered By:	<input checked="" type="checkbox"/> FedEx	<input type="checkbox"/> UPS	<input type="checkbox"/> On Trac
Preservation:	<input checked="" type="checkbox"/> Ice	<input type="checkbox"/> Blue Ice	<input type="checkbox"/> Dry Ice
Temp °C: 5.6 (uncorrected)	Time: 0919	Thermometer ID: IR-1	
Temp °C: 5.3 (corrected)	Probe used: Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>		

	YES	NO	NA
Adequate Sample Volume Received? A,B,C	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Holding Time Acceptable?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Shipping Container(s) Intact?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Shipping Custody Seals Intact?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Shipping Documentation Present?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Airbill Trk # 7843 6886 4525	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Sample Container Intact?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
Sample Custody Seals Intact?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Chain of Custody / Sample Documentation Present?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>
COC Anomaly/Sample Acceptance Form completed?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>
If Chlorinated or Drinking Water Samples, Acceptable Preservation?	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>
Preservation Documented:	Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub>	Trizma	Yes No NA
Shipping Container	Vista	Client	Retain Return Dispose

Comments:



January 03, 2017

**Vista Work Order No. 1601548**

Mr. Scott Bourne  
CDIM Engineering  
45 Polk Street, 3rd Floor  
San Francisco, CA 94102

Dear Mr. Bourne,

Enclosed are the results for the sample set received at Vista Analytical Laboratory on December 09, 2016. This sample set was analyzed on a standard turn-around time, under your Project Name '101-001-LRTC, Task 1'.

Vista Analytical Laboratory is committed to serving you effectively. If you require additional information, please contact me at 916-673-1520 or by email at [mmaier@vista-analytical.com](mailto:mmaier@vista-analytical.com).

Thank you for choosing Vista as part of your analytical support team.

Sincerely,

*Karen Lopez* for

Martha Maier  
Laboratory Director



*Vista Analytical Laboratory certifies that the report herein meets all the requirements set forth by NELAP for those applicable test methods. Results relate only to the samples as received by the laboratory. This report should not be reproduced except in full without the written approval of Vista.*

**Vista Work Order No. 1601548****Case Narrative****Sample Condition on Receipt:**

One water sample was received in good condition and within the method temperature requirements. The sample was received and stored securely in accordance with Vista standard operating procedures and EPA methodology.

**Analytical Notes:****EPA Method 1699**

The sample was extracted and analyzed for chlorinated pesticides by EPA Method 1699 using a ZB-50 GC column.

**Holding Times**

The sample was extracted and analyzed within the method hold times.

**Quality Control**

The Initial Calibration and Continuing Calibration Verifications met the method acceptance criteria.

A Method Blank and Ongoing Precision and Recovery (OPR) sample were extracted and analyzed with the preparation batch. The recovery of 13C12-Methoxychlor and 13C10-Mirex were outside of the method acceptance criteria in the Method Blank and OPR; these analytes were not detected in the field sample. All other OPR recoveries were within the method acceptance criteria.

The labeled standard recoveries for all QC and field samples were within the acceptance criteria.

**QC Anomalies**

LabNumber	SampleName	Analysis	Analyte	Flag	%Rec
1601548-01	TS2-E-161208	EPA Method 1699	13C12-2,4'-DDE	H	43.4
1601548-01	TS2-E-161208	EPA Method 1699	13C12-4,4'-DDE	H	32.4
1601548-01	TS2-E-161208	EPA Method 1699	13C10-cis-Nonachlor	H	23.0
B6L0072-BLK1	B6L0072-BLK1	EPA Method 1699	13C12-Methoxychlor	H	176
B6L0072-BLK1	B6L0072-BLK1	EPA Method 1699	13C10-Mirex	H	142
B6L0072-BS1	B6L0072-BS1	EPA Method 1699	13C12-Methoxychlor	H	204
B6L0072-BS1	B6L0072-BS1	EPA Method 1699	13C10-Mirex	H	180
B6L0072-BS1	B6L0072-BS1	EPA Method 1699	13C12-Endrin Ketone	H	151

H = Recovery was outside laboratory acceptance criteria.



## TABLE OF CONTENTS

Case Narrative.....	1
Table of Contents.....	3
Sample Inventory.....	4
Analytical Results.....	5
Qualifiers.....	9
Certifications.....	10
Sample Receipt.....	13

# Sample Inventory Report

Vista Sample ID	Client Sample ID	Sampled	Received	Components/Containers
1601548-01	TS2-E-161208	08-Dec-16 09:05	09-Dec-16 09:37	Amber Glass NM Bottle, 1L Amber Glass NM Bottle, 1L Amber Glass NM Bottle, 1L

## **ANALYTICAL RESULTS**

Sample ID: Method Blank					EPA Method 1699				
Matrix: Aqueous		QC Batch: B6L0072			Lab Sample: B6L0072-BLK1				
Sample Size: 1.00 L		Date Extracted: 14-Dec-2016 7:30			Date Analyzed: 28-Dec-16 14:38 Column: ZB-50				
Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers	
Hexachlorobenzene	3.25			J	IS 13C6-Hexachlorobenzene	66.3	5 - 120		
alpha-BHC	ND	5.34			IS 13C6-alpha-BHC	93.7	32 - 130		
Lindane (gamma-BHC)	ND	9.07			IS 13C6-Lindane (gamma-BHC)	91.7	11 - 120		
beta-BHC	ND	9.60			IS 13C6-beta-BHC	90.3	32 - 130		
delta-BHC	ND	6.38			IS 13C6-delta-BHC	89.6	36 - 137		
Heptachlor	ND	5.66			IS 13C10-Heptachlor	71.4	5 - 120		
Aldrin	ND	3.24			IS 13C12-Aldrin	58.1	5 - 120		
Oxychlordane	ND	11.5			IS 13C10-Oxychlordane	58.7	23 - 135		
cis-Heptachlor Epoxide	ND	9.05			IS 13C10-cis-Heptachlor Epoxide	57.1	27 - 137		
trans-Heptachlor Epoxide	ND	31.4			IS 13C10-trans-Chlordane (gamma)	69.8	21 - 132		
trans-Chlordane (gamma)	ND	10.7			IS 13C10-trans-Nonachlor	68.8	14 - 136		
trans-Nonachlor	ND	8.64			IS 13C9-Endosulfan I (alpha)	67.8	15 - 148		
cis-Chlordane (alpha)	ND	8.41			IS 13C12-2,4'-DDE	68.8	47 - 160		
Endosulfan I (alpha)	ND	12.8			IS 13C12-4,4'-DDE	71.8	47 - 160		
2,4'-DDE	ND	2.51			IS 13C12-Dieldrin	74.6	40 - 151		
4,4'-DDE	ND	2.53			IS 13C12-Endrin	59.0	35 - 155		
Dieldrin	ND	3.19			IS 13C10-cis-Nonachlor	62.9	36 - 139		
Endrin	ND	13.1			IS 13C9-Endosulfan II (beta)	50.1	5 - 122		
cis-Nonachlor	ND	6.27			IS 13C12-2,4'-DDD	100	5 - 199		
Endosulfan II (beta)	ND	27.7			IS 13C12-2,4'-DDT	104	5 - 199		
2,4'-DDD	ND	3.69			IS 13C12-4,4'-DDD	99.2	5 - 120		
2,4'-DDT	ND	8.58			IS 13C12-4,4'-DDT	100	5 - 120		
4,4'-DDD	ND	3.76			IS 13C9-Endosulfan Sulfate	46.0	15 - 148		
4,4'-DDT	ND	9.06			IS 13C12-Methoxychlor	176	5 - 120		H
Endosulfan Sulfate	ND	20.6			IS 13C10-Mirex	142	5 - 120		H
4,4'-Methoxychlor	ND	4.78			IS 13C12-Endrin Aldehyde	26.5	15 - 148		
Mirex	ND	1.78			IS 13C12-Endrin Ketone	133	15 - 148		
Endrin Aldehyde	ND	45.5							
Endrin Ketone	ND	20.9							

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Sample ID: OPR

EPA Method 1699

Matrix: Aqueous  
Sample Size: 1.00 LQC Batch: B6L0072  
Date Extracted: 14-Dec-2016 7:30Lab Sample: B6L0072-BS1  
Date Analyzed: 28-Dec-16 11:20 Column: ZB-50

Analyte	Amt Found (pg/L)	Spike Amt	%R	Limits	Labeled Standard	%R	LCL-UCL
Hexachlorobenzene	1050	1000	105	50 - 120	IS 13C6-Hexachlorobenzene	79.1	5 - 120
alpha-BHC	1070	1000	107	50 - 120	IS 13C6-alpha-BHC	124	17 - 141
Lindane (gamma-BHC)	1030	1000	103	50 - 120	IS 13C6-Lindane (gamma-BHC)	118	5 - 124
beta-BHC	1060	1000	106	50 - 120	IS 13C6-beta-BHC	107	17 - 141
delta-BHC	1040	1000	104	50 - 120	IS 13C6-delta-BHC	108	16 - 150
Heptachlor	967	1000	96.7	50 - 120	IS 13C10-Heptachlor	88.6	5 - 128
Aldrin	1010	1000	101	50 - 120	IS 13C12-Aldrin	63.3	5 - 126
Oxychlordane	893	1000	89.3	50 - 120	IS 13C10-Oxychlordane	71.0	5 - 144
cis-Heptachlor Epoxide	1030	1000	103	50 - 120	IS 13C10-cis-Heptachlor Epoxide	58.0	8 - 146
trans-Heptachlor Epoxide	1010	1000	101	50 - 120	IS 13C10-trans-Chlordane (gamma)	81.2	15 - 144
trans-Chlordane (gamma)	1020	1000	102	50 - 120	IS 13C10-trans-Nonachlor	86.6	13 - 149
trans-Nonachlor	947	1000	94.7	50 - 120	IS 13C9-Endosulfan I (alpha)	76.9	5 - 144
cis-Chlordane (alpha)	976	1000	97.6	50 - 120	IS 13C12-2,4'-DDE	77.5	26 - 169
Endosulfan I (alpha)	955	1000	95.5	50 - 120	IS 13C12-4,4'-DDE	77.8	26 - 169
2,4'-DDE	1070	1000	107	24 - 123	IS 13C12-Dieldrin	92.1	19 - 161
4,4'-DDE	995	1000	99.5	50 - 120	IS 13C12-Endrin	70.0	20 - 157
Dieldrin	1040	1000	104	50 - 120	IS 13C10-cis-Nonachlor	66.6	17 - 154
Endrin	1080	1000	108	50 - 120	IS 13C9-Endosulfan II (beta)	62.5	5 - 120
cis-Nonachlor	1110	1000	111	50 - 120	IS 13C12-2,4'-DDD	113	14 - 200
Endosulfan II (beta)	991	1000	99.1	5 - 200	IS 13C12-2,4'-DDT	130	14 - 200
2,4'-DDD	1130	1000	113	50 - 120	IS 13C12-4,4'-DDD	114	14 - 200
2,4'-DDT	1110	1000	111	50 - 120	IS 13C12-4,4'-DDT	120	13 - 200
4,4'-DDD	1070	1000	107	42 - 120	IS 13C9-Endosulfan Sulfate	55.0	5 - 144
4,4'-DDT	1130	1000	113	50 - 120	IS 13C12-Methoxychlor	204	8 - 200
Endosulfan Sulfate	971	1000	97.1	50 - 120	IS 13C10-Mirex	180	5 - 138
4,4'-Methoxychlor	1020	1000	102	50 - 120	IS 13C12-Endrin Aldehyde	27.6	5 - 144
Mirex	1020	1000	102	50 - 120	IS 13C12-Endrin Ketone	151	5 - 144
Endrin Aldehyde	1270	1000	127	50 - 134			
Endrin Ketone	955	1000	95.5	50 - 134			

LCL-UCL - Lower control limit - upper control limit

Sample ID: TS2-E-161208

EPA Method 1699

Client Data			Sample Data		Laboratory Data			
Name:	CDIM Engineering		Matrix:	Water	Lab Sample:	1601548-01	Date Received:	09-Dec-2016 9:37
Project:	101-001-LRTC, Task 1		Sample Size:	0.987 L	QC Batch:	B6L0072	Date Extracted:	14-Dec-2016 7:30
Date Collected:	08-Dec-2016 9:05				Date Analyzed:	29-Dec-16 05:35	Column:	ZB-50
Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Hexachlorobenzene	67.1			B	IS 13C6-Hexachlorobenzene	84.2	5 - 120	
alpha-BHC	75.5				IS 13C6-alpha-BHC	122	32 - 130	
Lindane (gamma-BHC)	86.8				IS 13C6-Lindane (gamma-BHC)	113	11 - 120	
beta-BHC	69.2				IS 13C6-beta-BHC	90.8	32 - 130	
delta-BHC	ND	5.59			IS 13C6-delta-BHC	83.8	36 - 137	
Heptachlor	ND	9.54			IS 13C10-Heptachlor	111	5 - 120	
Aldrin	ND	5.55			IS 13C12-Aldrin	60.2	5 - 120	
Oxychlordane	ND	23.8			IS 13C10-Oxychlordane	58.7	23 - 135	
cis-Heptachlor Epoxide	60.9				IS 13C10-cis-Heptachlor Epoxide	51.1	27 - 137	
trans-Heptachlor Epoxide	121				IS 13C10-trans-Chlordane (gamma)	46.6	21 - 132	
trans-Chlordane (gamma)	ND		72.8		IS 13C10-trans-Nonachlor	45.7	14 - 136	
trans-Nonachlor	58.3				IS 13C9-Endosulfan I (alpha)	45.1	15 - 148	
cis-Chlordane (alpha)	ND		134		IS 13C12-2,4'-DDE	43.4	47 - 160	H
Endosulfan I (alpha)	ND	42.7			IS 13C12-4,4'-DDE	32.4	47 - 160	H
2,4'-DDE	25.5			J	IS 13C12-Dieldrin	40.8	40 - 151	
4,4'-DDE	381				IS 13C12-Endrin	41.2	35 - 155	
Dieldrin	1460				IS 13C10-cis-Nonachlor	23.0	36 - 139	H
Endrin	470				IS 13C9-Endosulfan II (beta)	28.1	5 - 122	
cis-Nonachlor	ND	52.0			IS 13C12-2,4'-DDD	51.4	5 - 199	
Endosulfan II (beta)	ND	168			IS 13C12-2,4'-DDT	45.8	5 - 199	
2,4'-DDD	194				IS 13C12-4,4'-DDD	31.9	5 - 120	
2,4'-DDT	233				IS 13C12-4,4'-DDT	29.4	5 - 120	
4,4'-DDD	410				IS 13C9-Endosulfan Sulfate	44.9	15 - 148	
4,4'-DDT	951				IS 13C12-Methoxychlor	65.2	5 - 120	
Endosulfan Sulfate	ND	306			IS 13C10-Mirex	37.5	5 - 120	
4,4'-Methoxychlor	ND	241			IS 13C12-Endrin Aldehyde	26.7	15 - 148	
Mirex	ND	30.9			IS 13C12-Endrin Ketone	43.0	15 - 148	
Endrin Aldehyde	ND	220						
Endrin Ketone	726							

DL - Sample specific estimated detection limit

LCL-UCL - Lower control limit - upper control limit

EMPC - Estimated maximum possible concentration



## **DATA QUALIFIERS & ABBREVIATIONS**

<b>B</b>	<b>This compound was also detected in the method blank.</b>
<b>D</b>	<b>Dilution</b>
<b>E</b>	<b>The associated compound concentration exceeded the calibration range of the instrument.</b>
<b>H</b>	<b>Recovery and/or RPD was outside laboratory acceptance limits.</b>
<b>I</b>	<b>Chemical Interference</b>
<b>J</b>	<b>The amount detected is below the Reporting Limit/LOQ.</b>
<b>M</b>	<b>Estimated Maximum Possible Concentration. (CA Region 2 projects only)</b>
<b>*</b>	<b>See Cover Letter</b>
<b>Conc.</b>	<b>Concentration</b>
<b>NA</b>	<b>Not applicable</b>
<b>ND</b>	<b>Not Detected</b>
<b>TEQ</b>	<b>Toxic Equivalency</b>

**Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.**

## **CERTIFICATIONS**

<b>Accrediting Authority</b>	<b>Certificate Number</b>
California Department of Health – ELAP	2892
DoD ELAP - A2LA Accredited - ISO/IEC 17025:2005	3091.01
Florida Department of Health	E87777
Hawaii Department of Health	N/A
Louisiana Department of Environmental Quality	01977
Maine Department of Health	2014022
Nevada Division of Environmental Protection	CA004132015-1
New Jersey Department of Environmental Protection	CA003
New York Department of Health	11411
Oregon Laboratory Accreditation Program	4042-004
Pennsylvania Department of Environmental Protection	012
South Carolina Department of Health	87002001
Texas Commission on Environmental Quality	T104704189-15-6
Virginia Department of General Services	7923
Washington Department of Ecology	C584
Wisconsin Department of Natural Resources	998036160

*Current certificates and lists of licensed parameters are located in the Quality Assurance office and are available upon request*

## NELAP Accredited Test Methods

MATRIX: Air	
Description of Test	Method
Determination of Polychlorinated p-Dioxins & Polychlorinated Dibenzofurans	EPA 23

MATRIX: Biological Tissue	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Drinking Water	
Description of Test	Method
2,3,7,8-Tetrachlorodibenzo- p-dioxin (2,3,7,8-TCDD) GC/HRMS	EPA 1613
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537

MATRIX: Non-Potable Water	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Dioxin by GC/HRMS	EPA 613
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Solids	
Description of Test	Method
Tetra-Octa Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope	EPA 1613B

Dilution GC/HRMS	
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A





# SAMPLE LOG-IN CHECKLIST



Vista Project #:

1601548

TAT

Std

Samples Arrival:	Date/Time	Initials:	Location:
	12/09/16 0937	WJB	WR 2
Logged In:	Date/Time	Initials:	Location:
	12/09/16 1616	WJB	WR-2
Delivered By:	FedEx	UPS	On Trac
	DHL	Hand Delivered	Other
Preservation:	Ice	Blue Ice	Dry Ice
			None
Temp °C: 4.8	(uncorrected)	Time: 0940	Thermometer ID: IR-1
Temp °C: 4.5	(corrected)	Probe used: Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	

	YES	NO	NA
Adequate Sample Volume Received?	✓		
Holding Time Acceptable?	✓		
Shipping Container(s) Intact?	✓		
Shipping Custody Seals Intact?			✓
Shipping Documentation Present?	✓		
Airbill	✓		
Trk #			
Sample Container Intact?	✓		
Sample Custody Seals Intact?			✓
Chain of Custody / Sample Documentation Present?	✓		
COC Anomaly/Sample Acceptance Form completed?		✓	
If Chlorinated or Drinking Water Samples, Acceptable Preservation?			✓
Preservation Documented:	Yes	No	NA
Shipping Container	Vista	Client	Retain
		Return	Dispose

Comments:



January 12, 2017

**Vista Work Order No. 1700005**

Mr. Scott Bourne  
CDIM Engineering  
45 Polk Street, 3rd Floor  
San Francisco, CA 94102

Dear Mr. Bourne,

Enclosed are the results for the sample set received at Vista Analytical Laboratory on January 04, 2017. This sample set was analyzed on a standard turn-around time, under your Project Name 'LRTC Annual Storm Water Sampling'.

Vista Analytical Laboratory is committed to serving you effectively. If you require additional information, please contact me at 916-673-1520 or by email at [mmaier@vista-analytical.com](mailto:mmaier@vista-analytical.com).

Thank you for choosing Vista as part of your analytical support team.

Sincerely,

Martha Maier  
Laboratory Director



*Vista Analytical Laboratory certifies that the report herein meets all the requirements set forth by NELAP for those applicable test methods. Results relate only to the samples as received by the laboratory. This report should not be reproduced except in full without the written approval of Vista.*

**Vista Work Order No. 1700005****Case Narrative****Sample Condition on Receipt:**

One water sample was received in good condition and within the method temperature requirements. The sample was received and stored securely in accordance with Vista standard operating procedures and EPA methodology.

**Analytical Notes:****EPA Method 1699**

The sample was extracted and analyzed for chlorinated pesticides by EPA Method 1699 using a ZB-50 GC column.

**Holding Times**

The sample was extracted and analyzed within the method hold times.

**Quality Control**

The Initial Calibration and Continuing Calibration Verifications met the method acceptance criteria.

A Method Blank and Ongoing Precision and Recovery (OPR) sample were extracted and analyzed with the preparation batch. No analytes were detected above the sample quantitation limits in the Method Blank. The OPR recoveries were within the method acceptance criteria.

Labeled standard recoveries for all QC and field samples were within method acceptance criteria.

## TABLE OF CONTENTS

Case Narrative.....	1
Table of Contents.....	3
Sample Inventory.....	4
Analytical Results.....	5
Qualifiers.....	9
Certifications.....	10
Sample Receipt.....	13

# Sample Inventory Report

Vista Sample ID	Client Sample ID	Sampled	Received	Components/Containers
1700005-01	TS2-E-170103	03-Jan-17 12:15	04-Jan-17 10:11	Amber Glass NM Bottle, 1L Amber Glass NM Bottle, 1L Amber Glass NM Bottle, 1L



## **ANALYTICAL RESULTS**

Sample ID: Method Blank					EPA Method 1699				
Matrix: Aqueous		QC Batch: B7A0011			Lab Sample: B7A0011-BLK1				
Sample Size: 1.00 L		Date Extracted: 05-Jan-2017 8:21			Date Analyzed: 06-Jan-17 23:06 Column: ZB-50				
Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers	
Hexachlorobenzene	ND		3.13		IS 13C6-Hexachlorobenzene	65.4	5 - 120		
alpha-BHC	ND	4.96			IS 13C6-alpha-BHC	79.5	32 - 130		
Lindane (gamma-BHC)	ND	8.79			IS 13C6-Lindane (gamma-BHC)	81.3	11 - 120		
beta-BHC	ND	7.62			IS 13C6-beta-BHC	91.1	32 - 130		
delta-BHC	ND	5.79			IS 13C6-delta-BHC	91.2	36 - 137		
Heptachlor	ND	1.94			IS 13C10-Heptachlor	62.1	5 - 120		
Aldrin	ND	1.42			IS 13C12-Aldrin	81.4	5 - 120		
Oxychlordane	ND	5.32			IS 13C10-Oxychlordane	90.6	23 - 135		
cis-Heptachlor Epoxide	ND	4.11			IS 13C10-cis-Heptachlor Epoxide	84.9	27 - 137		
trans-Heptachlor Epoxide	ND	9.98			IS 13C10-trans-Chlordane (gamma)	89.0	21 - 132		
trans-Chlordane (gamma)	ND	3.83			IS 13C10-trans-Nonachlor	78.0	14 - 136		
trans-Nonachlor	ND	3.66			IS 13C9-Endosulfan I (alpha)	79.4	15 - 148		
cis-Chlordane (alpha)	ND	3.65			IS 13C12-2,4'-DDE	89.7	47 - 160		
Endosulfan I (alpha)	ND	5.92			IS 13C12-4,4'-DDE	95.7	47 - 160		
2,4'-DDE	ND	1.82			IS 13C12-Dieldrin	90.9	40 - 151		
4,4'-DDE	ND	2.00			IS 13C12-Endrin	88.9	35 - 155		
Dieldrin	ND	1.92			IS 13C10-cis-Nonachlor	89.1	36 - 139		
Endrin	ND	5.37			IS 13C9-Endosulfan II (beta)	85.6	5 - 122		
cis-Nonachlor	ND	4.02			IS 13C12-2,4'-DDD	98.5	5 - 199		
Endosulfan II (beta)	ND	11.9			IS 13C12-2,4'-DDT	96.5	5 - 199		
2,4'-DDD	ND	1.95			IS 13C12-4,4'-DDD	98.1	5 - 120		
2,4'-DDT	ND	3.81			IS 13C12-4,4'-DDT	96.6	5 - 120		
4,4'-DDD	ND	2.08			IS 13C9-Endosulfan Sulfate	88.9	15 - 148		
4,4'-DDT	ND	4.02			IS 13C12-Methoxychlor	81.3	5 - 120		
Endosulfan Sulfate	ND	8.30			IS 13C10-Mirex	87.1	5 - 120		
4,4'-Methoxychlor	ND	3.57			IS 13C12-Endrin Aldehyde	69.9	15 - 148		
Mirex	ND	1.38			IS 13C12-Endrin Ketone	82.1	15 - 148		
Endrin Aldehyde	ND	7.71							
Endrin Ketone	ND	11.9							

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Sample ID: OPR

EPA Method 1699

Matrix: Aqueous  
Sample Size: 1.00 LQC Batch: B7A0011  
Date Extracted: 05-Jan-2017 8:21Lab Sample: B7A0011-BS1  
Date Analyzed: 06-Jan-17 21:31 Column: ZB-50

Analyte	Amt Found (pg/L)	Spike Amt	%R	Limits	Labeled Standard	%R	LCL-UCL
Hexachlorobenzene	998	1000	99.8	50 - 120	IS 13C6-Hexachlorobenzene	71.2	5 - 120
alpha-BHC	985	1000	98.5	50 - 120	IS 13C6-alpha-BHC	84.5	17 - 141
Lindane (gamma-BHC)	1050	1000	105	50 - 120	IS 13C6-Lindane (gamma-BHC)	88.9	5 - 124
beta-BHC	996	1000	99.6	50 - 120	IS 13C6-beta-BHC	103	17 - 141
delta-BHC	930	1000	93.0	50 - 120	IS 13C6-delta-BHC	105	16 - 150
Heptachlor	1170	1000	117	50 - 120	IS 13C10-Heptachlor	72.9	5 - 128
Aldrin	950	1000	95.0	50 - 120	IS 13C12-Aldrin	90.3	5 - 126
Oxychlordane	1060	1000	106	50 - 120	IS 13C10-Oxychlordane	94.6	5 - 144
cis-Heptachlor Epoxide	1050	1000	105	50 - 120	IS 13C10-cis-Heptachlor Epoxide	97.6	8 - 146
trans-Heptachlor Epoxide	873	1000	87.3	50 - 120	IS 13C10-trans-Chlordane (gamma)	99.1	15 - 144
trans-Chlordane (gamma)	979	1000	97.9	50 - 120	IS 13C10-trans-Nonachlor	94.8	13 - 149
trans-Nonachlor	928	1000	92.8	50 - 120	IS 13C9-Endosulfan I (alpha)	94.3	5 - 144
cis-Chlordane (alpha)	1020	1000	102	50 - 120	IS 13C12-2,4'-DDE	96.3	26 - 169
Endosulfan I (alpha)	995	1000	99.5	50 - 120	IS 13C12-4,4'-DDE	100	26 - 169
2,4'-DDE	952	1000	95.2	24 - 123	IS 13C12-Dieldrin	88.9	19 - 161
4,4'-DDE	893	1000	89.3	50 - 120	IS 13C12-Endrin	89.7	20 - 157
Dieldrin	1010	1000	101	50 - 120	IS 13C10-cis-Nonachlor	105	17 - 154
Endrin	1140	1000	114	50 - 120	IS 13C9-Endosulfan II (beta)	98.5	5 - 120
cis-Nonachlor	941	1000	94.1	50 - 120	IS 13C12-2,4'-DDD	109	14 - 200
Endosulfan II (beta)	940	1000	94.0	5 - 200	IS 13C12-2,4'-DDT	112	14 - 200
2,4'-DDD	976	1000	97.6	50 - 120	IS 13C12-4,4'-DDD	111	14 - 200
2,4'-DDT	970	1000	97.0	50 - 120	IS 13C12-4,4'-DDT	114	13 - 200
4,4'-DDD	998	1000	99.8	42 - 120	IS 13C9-Endosulfan Sulfate	93.5	5 - 144
4,4'-DDT	991	1000	99.1	50 - 120	IS 13C12-Methoxychlor	103	8 - 200
Endosulfan Sulfate	1100	1000	110	50 - 120	IS 13C10-Mirex	104	5 - 138
4,4'-Methoxychlor	965	1000	96.5	50 - 120	IS 13C12-Endrin Aldehyde	75.0	5 - 144
Mirex	966	1000	96.6	50 - 120	IS 13C12-Endrin Ketone	101	5 - 144
Endrin Aldehyde	1040	1000	104	50 - 134			
Endrin Ketone	925	1000	92.5	50 - 134			

LCL-UCL - Lower control limit - upper control limit

Sample ID: TS2-E-170103

EPA Method 1699

Client Data			Sample Data		Laboratory Data			
Name:	CDIM Engineering		Matrix:	Water	Lab Sample:	1700005-01	Date Received:	04-Jan-2017 10:11
Project:	LRTC Annual Storm Water Sampling		Sample Size:	1.00 L	QC Batch:	B7A0011	Date Extracted:	05-Jan-2017 8:21
Date Collected:	03-Jan-2017 12:15				Date Analyzed:	07-Jan-17 03:05	Column:	ZB-50
Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Hexachlorobenzene	27.9			J	IS 13C6-Hexachlorobenzene	75.7	5 - 120	
alpha-BHC	41.4				IS 13C6-alpha-BHC	81.6	32 - 130	
Lindane (gamma-BHC)	88.1				IS 13C6-Lindane (gamma-BHC)	90.8	11 - 120	
beta-BHC	57.8				IS 13C6-beta-BHC	98.1	32 - 130	
delta-BHC	ND	5.38			IS 13C6-delta-BHC	103	36 - 137	
Heptachlor	ND	11.1			IS 13C10-Heptachlor	81.0	5 - 120	
Aldrin	ND	3.83			IS 13C12-Aldrin	92.2	5 - 120	
Oxychlordane	ND	18.3			IS 13C10-Oxychlordane	95.0	23 - 135	
cis-Heptachlor Epoxide	ND		123		IS 13C10-cis-Heptachlor Epoxide	99.8	27 - 137	
trans-Heptachlor Epoxide	804				IS 13C10-trans-Chlordane (gamma)	90.6	21 - 132	
trans-Chlordane (gamma)	ND		87.6		IS 13C10-trans-Nonachlor	90.5	14 - 136	
trans-Nonachlor	54.3				IS 13C9-Endosulfan I (alpha)	92.2	15 - 148	
cis-Chlordane (alpha)	223				IS 13C12-2,4'-DDE	95.2	47 - 160	
Endosulfan I (alpha)	ND	15.6			IS 13C12-4,4'-DDE	102	47 - 160	
2,4'-DDE	27.6			J	IS 13C12-Dieldrin	91.0	40 - 151	
4,4'-DDE	207				IS 13C12-Endrin	88.4	35 - 155	
Dieldrin	1300				IS 13C10-cis-Nonachlor	93.8	36 - 139	
Endrin	356				IS 13C9-Endosulfan II (beta)	77.9	5 - 122	
cis-Nonachlor	ND	10.1			IS 13C12-2,4'-DDD	130	5 - 199	
Endosulfan II (beta)	ND	40.5			IS 13C12-2,4'-DDT	82.5	5 - 199	
2,4'-DDD	378				IS 13C12-4,4'-DDD	97.1	5 - 120	
2,4'-DDT	307				IS 13C12-4,4'-DDT	67.3	5 - 120	
4,4'-DDD	770				IS 13C9-Endosulfan Sulfate	64.5	15 - 148	
4,4'-DDT	767				IS 13C12-Methoxychlor	37.1	5 - 120	
Endosulfan Sulfate	ND	23.6			IS 13C10-Mirex	57.5	5 - 120	
4,4'-Methoxychlor	ND	32.5			IS 13C12-Endrin Aldehyde	53.5	15 - 148	
Mirex	ND	2.36			IS 13C12-Endrin Ketone	50.2	15 - 148	
Endrin Aldehyde	ND	12.8						
Endrin Ketone	433							

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

## **DATA QUALIFIERS & ABBREVIATIONS**

<b>B</b>	<b>This compound was also detected in the method blank.</b>
<b>D</b>	<b>Dilution</b>
<b>E</b>	<b>The associated compound concentration exceeded the calibration range of the instrument.</b>
<b>H</b>	<b>Recovery and/or RPD was outside laboratory acceptance limits.</b>
<b>I</b>	<b>Chemical Interference</b>
<b>J</b>	<b>The amount detected is below the Reporting Limit/LOQ.</b>
<b>M</b>	<b>Estimated Maximum Possible Concentration. (CA Region 2 projects only)</b>
<b>*</b>	<b>See Cover Letter</b>
<b>Conc.</b>	<b>Concentration</b>
<b>NA</b>	<b>Not applicable</b>
<b>ND</b>	<b>Not Detected</b>
<b>TEQ</b>	<b>Toxic Equivalency</b>

**Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.**



## **CERTIFICATIONS**

<b>Accrediting Authority</b>	<b>Certificate Number</b>
California Department of Health – ELAP	2892
DoD ELAP - A2LA Accredited - ISO/IEC 17025:2005	3091.01
Florida Department of Health	E87777
Hawaii Department of Health	N/A
Louisiana Department of Environmental Quality	01977
Maine Department of Health	2014022
Nevada Division of Environmental Protection	CA004132015-1
New Jersey Department of Environmental Protection	CA003
New York Department of Health	11411
Oregon Laboratory Accreditation Program	4042-004
Pennsylvania Department of Environmental Protection	012
South Carolina Department of Health	87002001
Texas Commission on Environmental Quality	T104704189-15-6
Virginia Department of General Services	7923
Washington Department of Ecology	C584
Wisconsin Department of Natural Resources	998036160

*Current certificates and lists of licensed parameters are located in the Quality Assurance office and are available upon request*

## NELAP Accredited Test Methods

MATRIX: Air	
Description of Test	Method
Determination of Polychlorinated p-Dioxins & Polychlorinated Dibenzofurans	EPA 23

MATRIX: Biological Tissue	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Drinking Water	
Description of Test	Method
2,3,7,8-Tetrachlorodibenzo- p-dioxin (2,3,7,8-TCDD) GC/HRMS	EPA 1613
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537

MATRIX: Non-Potable Water	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Dioxin by GC/HRMS	EPA 613
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Solids	
Description of Test	Method
Tetra-Octa Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope	EPA 1613B

Dilution GC/HRMS	
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

**Vista Analytical**  
1104 Windfield Way  
El Dorado Hills, CA 95762  
Phone: (916) 673-1520

Please send analytic results, electronic deliverables  
and the original chain-of-custody form to:  
sab@cdimengineering.com  
mec@cdimengineering.com

**INSTRUCTIONS FOR LAB PERSONNEL:**

GeoTracker EDF required?      ☐ Yes      ☒ No

Equis 4-file EDWEDD required?   x   Yes ☐ No

Specify analytic/prep method and detection limit in report.

Notify us of any anomalous peaks in GC or other scans.

Call immediately with any questions or problems.

$$\begin{array}{r} 17000.05 \\ - 17000.04 \\ \hline 0.01 \end{array}$$
[illegible]

# SAMPLE LOG-IN CHECKLIST



Vista Project #: 1700005 TAT Std

Samples Arrival:	Date/Time <u>01/04/17</u> <u>1011</u>		Initials: <u>BBB</u>		Location: <u>WR-2</u>	
					Shelf/Rack: <u>NA</u>	
Logged In:	Date/Time <u>01/04/17</u> <u>1109</u>		Initials: <u>BBB</u>		Location: <u>WR-2</u>	
					Shelf/Rack: <u>B5</u>	
Delivered By:	<input checked="" type="checkbox"/> FedEx	<input type="checkbox"/> UPS	<input type="checkbox"/> On Trac	<input type="checkbox"/> DHL	<input type="checkbox"/> Hand Delivered	<input type="checkbox"/> Other
Preservation:	<input checked="" type="checkbox"/> Ice	<input type="checkbox"/> Blue Ice	<input type="checkbox"/> Dry Ice	<input type="checkbox"/> None		
Temp °C: <u>0.8</u> (uncorrected)	Time: <u>1025</u>		Thermometer ID: <u>IR-1</u>			
Temp °C: <u>0.5</u> (corrected)	Probe used: Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>					

		YES	NO	NA
Adequate Sample Volume Received? <u>A,B,C bottles</u>		<input checked="" type="checkbox"/>		
Holding Time Acceptable?		<input checked="" type="checkbox"/>		
Shipping Container(s) Intact?		<input checked="" type="checkbox"/>		
Shipping Custody Seals Intact?				<input checked="" type="checkbox"/>
Shipping Documentation Present?		<input checked="" type="checkbox"/>		
Airbill	Trk # <u>78 5208 338 350</u>	<input checked="" type="checkbox"/>		
Sample Container Intact?		<input checked="" type="checkbox"/>		
Sample Custody Seals Intact?				<input checked="" type="checkbox"/>
Chain of Custody / Sample Documentation Present?		<input checked="" type="checkbox"/>		
COC Anomaly/Sample Acceptance Form completed?			<input checked="" type="checkbox"/>	
If Chlorinated or Drinking Water Samples, Acceptable Preservation?				<input checked="" type="checkbox"/>
Preservation Documented:	<u>Na<sub>2</sub>S<sub>2</sub>O<sub>3</sub></u> <u>Trizma</u>	Yes	No	<input checked="" type="checkbox"/> NA
Shipping Container	<u>Vista</u> <u>Client</u> <u>Retain</u> <u>Return</u> <u>Dispose</u>			

Comments: "TS2-E-170103" A,B,C





February 10, 2017

**Vista Work Order No. 1700096**

Mr. Scott Bourne  
CDIM Engineering  
45 Polk Street, 3rd Floor  
San Francisco, CA 94102

Dear Mr. Bourne,

Enclosed are the results for the sample set received at Vista Analytical Laboratory on January 20, 2017. This sample set was analyzed on a standard turn-around time, under your Project Name '101-001-LRTC, Task 1'.

Vista Analytical Laboratory is committed to serving you effectively. If you require additional information, please contact me at 916-673-1520 or by email at [mmaier@vista-analytical.com](mailto:mmaier@vista-analytical.com).

Thank you for choosing Vista as part of your analytical support team.

Sincerely,

Martha Maier  
Laboratory Director



*Vista Analytical Laboratory certifies that the report herein meets all the requirements set forth by NELAP for those applicable test methods. Results relate only to the samples as received by the laboratory. This report should not be reproduced except in full without the written approval of Vista.*

**Vista Work Order No. 1700096****Case Narrative****Sample Condition on Receipt:**

One water sample was received in good condition and within the method temperature requirements. The sample was received and stored securely in accordance with Vista standard operating procedures and EPA methodology.

**Analytical Notes:****EPA Method 1699**

The sample was extracted and analyzed for chlorinated pesticides by EPA Method 1699 using a ZB-50 GC column.

**Holding Times**

The sample was extracted and analyzed within the method hold times.

**Quality Control**

The Initial Calibration and Continuing Calibration Verifications met the method acceptance criteria.

A Method Blank and Ongoing Precision and Recovery (OPR) sample were extracted and analyzed with the preparation batch. No analytes were detected above the sample quantitation limits in the Method Blank. The OPR recoveries were within the method acceptance criteria.

Labeled standard recoveries for all QC and field samples were within method acceptance criteria.

**QC Anomalies**

LabNumber	SampleName	Analysis	Analyte	Flag	%Rec
B7A0089-BLK1	B7A0089-BLK1	EPA Method 1699	13C12-4,4'-DDD	H	121
B7A0089-BLK1	B7A0089-BLK1	EPA Method 1699	13C10-Mirex	H	125
B7A0089-BLK1	B7A0089-BLK1	EPA Method 1699	13C12-Endrin Aldehyde	H	12.8

H = Recovery was outside laboratory acceptance criteria.

## TABLE OF CONTENTS

Case Narrative.....	1
Table of Contents.....	3
Sample Inventory.....	4
Analytical Results.....	5
Qualifiers.....	9
Certifications.....	10
Sample Receipt.....	13

# Sample Inventory Report

Vista Sample ID	Client Sample ID	Sampled	Received	Components/Containers
1700096-01	TS2-E-170118	18-Jan-17 14:05	20-Jan-17 09:29	Amber Glass NM Bottle, 1L Amber Glass NM Bottle, 1L Amber Glass NM Bottle, 1L

## **ANALYTICAL RESULTS**



Sample ID: Method Blank					EPA Method 1699				
Matrix: Aqueous		QC Batch: B7A0089			Lab Sample: B7A0089-BLK1				
Sample Size: 1.00 L		Date Extracted: 23-Jan-2017 8:57			Date Analyzed: 07-Feb-17 20:14 Column: ZB-50				
Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers	
Hexachlorobenzene	ND		3.71		IS 13C6-Hexachlorobenzene	61.9	5 - 120		
alpha-BHC	ND	5.91			IS 13C6-alpha-BHC	78.7	32 - 130		
Lindane (gamma-BHC)	ND	7.45			IS 13C6-Lindane (gamma-BHC)	85.0	11 - 120		
beta-BHC	ND	10.2			IS 13C6-beta-BHC	88.4	32 - 130		
delta-BHC	ND	7.57			IS 13C6-delta-BHC	87.7	36 - 137		
Heptachlor	ND	1.36			IS 13C10-Heptachlor	56.0	5 - 120		
Aldrin	ND	1.74			IS 13C12-Aldrin	56.4	5 - 120		
Oxychlordane	ND	3.78			IS 13C10-Oxychlordane	64.4	23 - 135		
cis-Heptachlor Epoxide	ND	3.23			IS 13C10-cis-Heptachlor Epoxide	63.1	27 - 137		
trans-Heptachlor Epoxide	ND	11.9			IS 13C10-trans-Chlordane (gamma)	69.5	21 - 132		
trans-Chlordane (gamma)	ND	3.42			IS 13C10-trans-Nonachlor	93.4	14 - 136		
trans-Nonachlor	ND	3.18			IS 13C9-Endosulfan I (alpha)	101	15 - 148		
cis-Chlordane (alpha)	ND	3.16			IS 13C12-2,4'-DDE	106	47 - 160		
Endosulfan I (alpha)	ND	4.94			IS 13C12-4,4'-DDE	102	47 - 160		
2,4'-DDE	ND	3.35			IS 13C12-Dieldrin	101	40 - 151		
4,4'-DDE	ND	4.13			IS 13C12-Endrin	77.4	35 - 155		
Dieldrin	ND	1.93			IS 13C10-cis-Nonachlor	104	36 - 139		
Endrin	ND	6.56			IS 13C9-Endosulfan II (beta)	43.3	5 - 122		
cis-Nonachlor	ND	2.96			IS 13C12-2,4'-DDD	124	5 - 199		
Endosulfan II (beta)	ND	21.6			IS 13C12-2,4'-DDT	104	5 - 199		
2,4'-DDD	ND	6.11			IS 13C12-4,4'-DDD	121	5 - 120		H
2,4'-DDT	ND	12.6			IS 13C12-4,4'-DDT	105	5 - 120		
4,4'-DDD	ND	6.92			IS 13C9-Endosulfan Sulfate	51.3	15 - 148		
4,4'-DDT	ND	13.1			IS 13C12-Methoxychlor	47.6	5 - 120		
Endosulfan Sulfate	ND	21.6			IS 13C10-Mirex	125	5 - 120		H
4,4'-Methoxychlor	ND	3.87			IS 13C12-Endrin Aldehyde	12.8	15 - 148		H
Mirex	ND	0.829			IS 13C12-Endrin Ketone	43.4	15 - 148		
Endrin Aldehyde	ND	43.0							
Endrin Ketone	ND	17.8							

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

Sample ID: OPR

EPA Method 1699

Matrix: Aqueous  
Sample Size: 1.00 LQC Batch: B7A0089  
Date Extracted: 23-Jan-2017 8:57Lab Sample: B7A0089-BS1  
Date Analyzed: 06-Feb-17 15:17 Column: ZB-50

Analyte	Amt Found (pg/L)	Spike Amt	%R	Limits	Labeled Standard	%R	LCL-UCL
Hexachlorobenzene	960	1000	96.0	50 - 120	IS 13C6-Hexachlorobenzene	69.1	5 - 120
alpha-BHC	940	1000	94.0	50 - 120	IS 13C6-alpha-BHC	72.4	17 - 141
Lindane (gamma-BHC)	948	1000	94.8	50 - 120	IS 13C6-Lindane (gamma-BHC)	74.4	5 - 124
beta-BHC	963	1000	96.3	50 - 120	IS 13C6-beta-BHC	77.9	17 - 141
delta-BHC	946	1000	94.6	50 - 120	IS 13C6-delta-BHC	85.3	16 - 150
Heptachlor	933	1000	93.3	50 - 120	IS 13C10-Heptachlor	53.2	5 - 128
Aldrin	941	1000	94.1	50 - 120	IS 13C12-Aldrin	56.6	5 - 126
Oxychlordane	996	1000	99.6	50 - 120	IS 13C10-Oxychlordane	65.2	5 - 144
cis-Heptachlor Epoxide	1030	1000	103	50 - 120	IS 13C10-cis-Heptachlor Epoxide	64.9	8 - 146
trans-Heptachlor Epoxide	1190	1000	119	50 - 120	IS 13C10-trans-Chlordane (gamma)	81.6	15 - 144
trans-Chlordane (gamma)	920	1000	92.0	50 - 120	IS 13C10-trans-Nonachlor	90.5	13 - 149
trans-Nonachlor	1060	1000	106	50 - 120	IS 13C9-Endosulfan I (alpha)	111	5 - 144
cis-Chlordane (alpha)	1140	1000	114	50 - 120	IS 13C12-2,4'-DDE	118	26 - 169
Endosulfan I (alpha)	872	1000	87.2	50 - 120	IS 13C12-4,4'-DDE	113	26 - 169
2,4'-DDE	944	1000	94.4	24 - 123	IS 13C12-Dieldrin	128	19 - 161
4,4'-DDE	935	1000	93.5	50 - 120	IS 13C12-Endrin	87.5	20 - 157
Dieldrin	991	1000	99.1	50 - 120	IS 13C10-cis-Nonachlor	103	17 - 154
Endrin	1010	1000	101	50 - 120	IS 13C9-Endosulfan II (beta)	101	5 - 120
cis-Nonachlor	1060	1000	106	50 - 120	IS 13C12-2,4'-DDD	103	14 - 200
Endosulfan II (beta)	896	1000	89.6	5 - 200	IS 13C12-2,4'-DDT	88.0	14 - 200
2,4'-DDD	987	1000	98.7	50 - 120	IS 13C12-4,4'-DDD	98.0	14 - 200
2,4'-DDT	997	1000	99.7	50 - 120	IS 13C12-4,4'-DDT	84.9	13 - 200
4,4'-DDD	983	1000	98.3	42 - 120	IS 13C9-Endosulfan Sulfate	105	5 - 144
4,4'-DDT	980	1000	98.0	50 - 120	IS 13C12-Methoxychlor	67.5	8 - 200
Endosulfan Sulfate	888	1000	88.8	50 - 120	IS 13C10-Mirex	112	5 - 138
4,4'-Methoxychlor	1040	1000	104	50 - 120	IS 13C12-Endrin Aldehyde	76.5	5 - 144
Mirex	997	1000	99.7	50 - 120	IS 13C12-Endrin Ketone	68.8	5 - 144
Endrin Aldehyde	919	1000	91.9	50 - 134			
Endrin Ketone	1050	1000	105	50 - 134			

LCL-UCL - Lower control limit - upper control limit

**Sample ID: TS2-E-170118**

**EPA Method 1699**

Client Data			Sample Data		Laboratory Data			
Name:	CDIM Engineering		Matrix:	Water	Lab Sample:	1700096-01	Date Received:	20-Jan-2017 9:29
Project:	101-001-LRTC, Task 1		Sample Size:	1.01 L	QC Batch:	B7A0089	Date Extracted:	23-Jan-2017 8:57
Date Collected:	18-Jan-2017 14:05				Date Analyzed:	06-Feb-17 22:31	Column: ZB-50	
Analyte	Conc. (pg/L)	DL	EMPC	Qualifiers	Labeled Standard	%R	LCL-UCL	Qualifiers
Hexachlorobenzene	29.1			J	IS 13C6-Hexachlorobenzene	14.4	5 - 120	
alpha-BHC	52.5				IS 13C6-alpha-BHC	83.5	32 - 130	
Lindane (gamma-BHC)	48.8				IS 13C6-Lindane (gamma-BHC)	87.8	11 - 120	
beta-BHC	191				IS 13C6-beta-BHC	94.4	32 - 130	
delta-BHC	ND	2.89			IS 13C6-delta-BHC	95.4	36 - 137	
Heptachlor	ND	2.02			IS 13C10-Heptachlor	98.1	5 - 120	
Aldrin	ND	5.49			IS 13C12-Aldrin	81.3	5 - 120	
Oxychlordane	ND	15.3			IS 13C10-Oxychlordane	91.4	23 - 135	
cis-Heptachlor Epoxide	204				IS 13C10-cis-Heptachlor Epoxide	91.3	27 - 137	
trans-Heptachlor Epoxide	803				IS 13C10-trans-Chlordane (gamma)	86.1	21 - 132	
trans-Chlordane (gamma)	132				IS 13C10-trans-Nonachlor	125	14 - 136	
trans-Nonachlor	60.4				IS 13C9-Endosulfan I (alpha)	113	15 - 148	
cis-Chlordane (alpha)	378				IS 13C12-2,4'-DDE	135	47 - 160	
Endosulfan I (alpha)	ND	21.0			IS 13C12-4,4'-DDE	126	47 - 160	
2,4'-DDE	24.2			J	IS 13C12-Dieldrin	140	40 - 151	
4,4'-DDE	191				IS 13C12-Endrin	139	35 - 155	
Dieldrin	2770				IS 13C10-cis-Nonachlor	103	36 - 139	
Endrin	769				IS 13C9-Endosulfan II (beta)	89.0	5 - 122	
cis-Nonachlor	ND	22.8			IS 13C12-2,4'-DDD	118	5 - 199	
Endosulfan II (beta)	ND	80.4			IS 13C12-2,4'-DDT	89.4	5 - 199	
2,4'-DDD	409				IS 13C12-4,4'-DDD	87.8	5 - 120	
2,4'-DDT	266				IS 13C12-4,4'-DDT	68.4	5 - 120	
4,4'-DDD	700				IS 13C9-Endosulfan Sulfate	63.9	15 - 148	
4,4'-DDT	619				IS 13C12-Methoxychlor	30.6	5 - 120	
Endosulfan Sulfate	ND	118			IS 13C10-Mirex	45.3	5 - 120	
4,4'-Methoxychlor	ND	16.1			IS 13C12-Endrin Aldehyde	57.2	15 - 148	
Mirex	ND	12.0			IS 13C12-Endrin Ketone	40.9	15 - 148	
Endrin Aldehyde	ND	47.5						
Endrin Ketone	1960							

DL - Sample specific estimated detection limit

EMPC - Estimated maximum possible concentration

LCL-UCL - Lower control limit - upper control limit

## **DATA QUALIFIERS & ABBREVIATIONS**

<b>B</b>	<b>This compound was also detected in the method blank.</b>
<b>D</b>	<b>Dilution</b>
<b>E</b>	<b>The associated compound concentration exceeded the calibration range of the instrument.</b>
<b>H</b>	<b>Recovery and/or RPD was outside laboratory acceptance limits.</b>
<b>I</b>	<b>Chemical Interference</b>
<b>J</b>	<b>The amount detected is below the Reporting Limit/LOQ.</b>
<b>M</b>	<b>Estimated Maximum Possible Concentration. (CA Region 2 projects only)</b>
<b>*</b>	<b>See Cover Letter</b>
<b>Conc.</b>	<b>Concentration</b>
<b>NA</b>	<b>Not applicable</b>
<b>ND</b>	<b>Not Detected</b>
<b>TEQ</b>	<b>Toxic Equivalency</b>

**Unless otherwise noted, solid sample results are reported in dry weight. Tissue samples are reported in wet weight.**

## **CERTIFICATIONS**

<b>Accrediting Authority</b>	<b>Certificate Number</b>
California Department of Health – ELAP	2892
DoD ELAP - A2LA Accredited - ISO/IEC 17025:2005	3091.01
Florida Department of Health	E87777
Hawaii Department of Health	N/A
Louisiana Department of Environmental Quality	01977
Maine Department of Health	2014022
Nevada Division of Environmental Protection	CA004132015-1
New Jersey Department of Environmental Protection	CA003
New York Department of Health	11411
Oregon Laboratory Accreditation Program	4042-004
Pennsylvania Department of Environmental Protection	012
South Carolina Department of Health	87002001
Texas Commission on Environmental Quality	T104704189-15-6
Virginia Department of General Services	7923
Washington Department of Ecology	C584
Wisconsin Department of Natural Resources	998036160

*Current certificates and lists of licensed parameters are located in the Quality Assurance office and are available upon request*

## NELAP Accredited Test Methods

MATRIX: Air	
Description of Test	Method
Determination of Polychlorinated p-Dioxins & Polychlorinated Dibenzofurans	EPA 23

MATRIX: Biological Tissue	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Drinking Water	
Description of Test	Method
2,3,7,8-Tetrachlorodibenzo- p-dioxin (2,3,7,8-TCDD) GC/HRMS	EPA 1613
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537

MATRIX: Non-Potable Water	
Description of Test	Method
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613B
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Pesticides in Water, Soil, Sediment, Biosolids, and Tissue by HRGC/HRMS	EPA 1699
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Dioxin by GC/HRMS	EPA 613
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

MATRIX: Solids	
Description of Test	Method
Tetra-Octa Chlorinated Dioxins and Furans by Isotope Dilution GC/HRMS	EPA 1613
Tetra- through Octa-Chlorinated Dioxins and Furans by Isotope	EPA 1613B



Dilution GC/HRMS	
Brominated Diphenyl Ethers by HRGC/HRMS	EPA 1614A
Chlorinated Biphenyl Congeners in Water, Soil, Sediment, and Tissue by GC/HRMS	EPA 1668A/C
Perfluorinated Alkyl Acids in Drinking Water by SPE and LC/MS/MS	EPA 537
Polychlorinated Dibenzo-p-Dioxins and Polychlorinated Dibenzofurans by GC/HRMS	EPA 8280A/B
Polychlorinated Dibenzodioxins (PCDDs) and Polychlorinated Dibenzofurans (PCDFs) by GC/HRMS	EPA 8290/8290A

### Chain of Custody Record

**Vista Analytical**  
1104 Windfield Way  
El Dorado Hills, CA 95762  
**Phone: (916) 673-1520**

Please send analytic results, electronic deliverables  
and the original chain-of-custody form to:  
sab@cdimengineering.com  
mec@cdimengineering.com

**INSTRUCTIONS FOR LAB PERSONNEL:**

GeoTracker EDF required?    ☐ Yes    ☒ No  
Equis 4-file EDWEDD required?    ☒ Yes    ☐ No  
Specify analytic/prep method and detection limit in report.  
Notify us of any anomalous peaks in GC or other scans.  
Call immediately with any questions or problems.

1700096  
0.6°C

[illegible]

x = Samples released to a secured, locked area.

● = Samples received from a secured, locked area

# SAMPLE LOG-IN CHECKLIST



Vista Project #:

1700096

TAT

Std

Samples Arrival:	Date/Time	Initials:	Location:
	01/20/17 0929	CRB	WR-2
Logged In:	Date/Time	Initials:	Location:
	01/20/17 1013	CRB	WR-2
Delivered By:	FedEx	UPS	On Trac
	DHL	Hand Delivered	Other
Preservation:	Ice	Blue Ice	Dry Ice
	None		
Temp °C:	0.9 (uncorrected)	Time: 0931	Thermometer ID: IR-1
Temp °C:	0.6 (corrected)	Probe used: Yes <input type="checkbox"/> No <input checked="" type="checkbox"/>	

	YES	NO	NA
Adequate Sample Volume Received?	<input checked="" type="checkbox"/>		
Holding Time Acceptable?	<input checked="" type="checkbox"/>		
Shipping Container(s) Intact?	<input checked="" type="checkbox"/>		
Shipping Custody Seals Intact?			<input checked="" type="checkbox"/>
Shipping Documentation Present?	<input checked="" type="checkbox"/>		
Airbill	<input checked="" type="checkbox"/>		
Trk #			
Sample Container Intact?	<input checked="" type="checkbox"/>		
Sample Custody Seals Intact?			<input checked="" type="checkbox"/>
Chain of Custody / Sample Documentation Present?	<input checked="" type="checkbox"/>		
COC Anomaly/Sample Acceptance Form completed?		<input checked="" type="checkbox"/>	
If Chlorinated or Drinking Water Samples, Acceptable Preservation?			<input checked="" type="checkbox"/>
Preservation Documented:	Na <sub>2</sub> S <sub>2</sub> O <sub>3</sub>	Trizma	Yes No NA
Shipping Container	Vista	Client	Retain Return Dispose

Comments:

## **APPENDIX C**

### **Upland Capping System Inspection Form**



**Former United Heckathorn Superfund Site Upland Capping System Inspection Form**  
**Levin Richmond Terminal, 402 Wright Avenue, Richmond, California**

**I. General Information**

**Site:** Former United Heckathorn Superfund Site, Levin Richmond Terminal  
**Inspector:** Mary Cunningham, PE and Scott Bourne, PE  
**Address:** 402 Wright Avenue, Richmond, CA  
**Organization:** CDIM Engineering  
**Date and time of inspection:**

**II. Upland Area Concrete Cap, Gravel Cover, and Drainage System Observations**

*Note significant cracks, holes, penetrations, damage, settlement, or any exposure of underlying soil in any component of the capping system.*

**North Main Terminal (SW-3)**

	Yes	No	N/A	Comments
Are concrete cap surfaces in adequate condition to promote effectiveness of the cap?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Are gravel cover surfaces in adequate condition to promote effectiveness of the cap?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Is storm water drainage infrastructure (interceptors, drain inlets) in adequate condition to prevent exposure of underlying soil to runoff?	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<input type="checkbox"/>	
Is accumulated sediment observed in the interceptors or drain inlets? If yes, note location and photograph.	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	<i>Interceptors not accessed during this inspection. Drain inlets have inlet protection.</i>
Are corrective actions required?	<input type="checkbox"/>	<input checked="" type="checkbox"/>	<input type="checkbox"/>	
Attach a photograph of areas requiring corrective action.	<input type="checkbox"/>	<input type="checkbox"/>	<input checked="" type="checkbox"/>	

Describe any recent repairs/maintenance:

*All interceptors in Upland Area cleaned prior to the 2016-2017 wet season. This is performed annually during dry weather and as-needed throughout the storm season.*

*Drain inlets are equipped with drain inlet filters, which are observed during regular BMP inspections of the site and replaced as-needed, or at least once per year prior to the wet season.*

*Concrete was added along dock to widen road (bents 1-20) in previous year. During 2016-2017, curbing was added. This did not result in exposure of underlying soil.*

Describe conditions and locations of the capping system which require attention:

*A large stockpile was present in the secondary storage area, so this area of the cap was not accessed for inspection.*

*Sinking/degraded pavement was observed in a small area to the south of the cap. While this is outside to fhte Heckathorn cap, LRTC plans to remove the affected section and re-pour concrete.*

Describe corrective actions required and their date(s) of implementation:

*None.*

Signature:

Date:

1 of 5

## Former United Heckathorn Superfund Site Upland Capping System Inspection Form

Levin Richmond Terminal, 402 Wright Avenue, Richmond, California

### North Main Terminal/United Heckathorn (SW-4)

Yes No N/A Comments

Are concrete cap surfaces in adequate condition to promote effectiveness of the cap?

☒ ☐ ☐

Are gravel cover surfaces in adequate condition to promote effectiveness of the cap?

☒ ☐ ☐

Is storm water drainage infrastructure (interceptors, drain inlets) in adequate condition to prevent exposure of underlying soil to runoff?

☒ ☐ ☐

Is accumulated sediment observed in the interceptors or drain inlets? If yes, note location and photograph.

☐ ☒ ☐

*Interceptors not accessed during this inspection. Drain inlets have inlet protection.*

Are corrective actions required?

☐ ☒ ☐

Attach a photograph of areas requiring corrective action.

☐ ☐ ☒

Describe any recent repairs/maintenance:

*LRTC installed asphalt between rail lines in SW-4 area to replace previously graveled area.*

*See SW-3 section for discussion of road widening work in this area.*

Describe conditions and locations of the capping system which require attention:

*A long seam and surficial cracking was noted in the roadway north of the secondary storage area. No change was observed from previous year, but it should continue to be monitored.*

Describe corrective actions required and their date(s) of implementation:

*None.*

## Former United Heckathorn Superfund Site Upland Capping System Inspection Form

Levin Richmond Terminal, 402 Wright Avenue, Richmond, California

### North Main Terminal/United Heckathorn (SW-5)

Yes No N/A Comments

Are concrete cap surfaces in adequate condition to promote effectiveness of the cap?

☒ ☐ ☐

Are gravel cover surfaces in adequate condition to promote effectiveness of the cap?

☒ ☐ ☐

Is storm water drainage infrastructure (interceptors, drain inlets) in adequate condition to prevent exposure of underlying soil to runoff?

☒ ☐ ☐

Is accumulated sediment observed in the interceptors or drain inlets? If yes, note location and photograph.

☐ ☒ ☐

*Interceptors not accessed during this inspection. Drain inlets have inlet protection.*

Are corrective actions required?

☐ ☒ ☐

Attach a photograph of areas requiring corrective action.

☐ ☐ ☒

Describe any recent repairs/maintenance:

*A roadway has been installed in the SW-5/SW-6 catchment areas. Work began in 2015-2016 reporting year with concrete placement, and was completed this year with asphalt paving. The road crosses rail tracks and replaced gravel areas, increasing the paved portion of the site.*

Describe conditions and locations of the capping system which require attention:

*Minor pavement deterioration noted adjacent to gate/guard shack. No change noted from previous years, but area should continue to be monitored.*

*Gravel cover should continue to be monitored, and additional gravel placed as needed.*

Describe corrective actions required and their date(s) of implementation:

*None.*

## Former United Heckathorn Superfund Site Upland Capping System Inspection Form

Levin Richmond Terminal, 402 Wright Avenue, Richmond, California

### North Main Terminal/United Heckathorn (SW-6)

Yes No N/A Comments

Are concrete cap surfaces in adequate condition to promote effectiveness of the cap?

☒ ☐ ☐

Are gravel cover surfaces in adequate condition to promote effectiveness of the cap?

☒ ☐ ☐

Is storm water drainage infrastructure (interceptors, drain inlets) in adequate condition to prevent exposure of underlying soil to runoff?

☒ ☐ ☐

Is accumulated sediment observed in the interceptors or drain inlets? If yes, note location and photograph.

☐ ☒ ☐

*Interceptors not accessed during this inspection. Drain inlets have inlet protection.*

Are corrective actions required?

☐ ☒ ☐

Attach a photograph of areas requiring corrective action.

☐ ☐ ☒

Describe any recent repairs/maintenance:

*See discussion of road paving in SW-5 section. No other repairs/maintenance.*

Describe conditions and locations of the capping system which require attention:

*Gravel cover should continue to be monitored, and additional gravel placed as needed.*

Describe corrective actions required and their date(s) of implementation:

*None.*



**Former United Heckathorn Superfund Site Upland Capping System Inspection Form**

**Levin Richmond Terminal, 402 Wright Avenue, Richmond, California**

**North Main Terminal/United Heckathorn (SW-7)**

**Yes No N/A Comments**

Are concrete cap surfaces in adequate condition to promote effectiveness of the cap?

☒ ☐ ☐

Are gravel cover surfaces in adequate condition to promote effectiveness of the cap?

☒ ☐ ☐

Is storm water drainage infrastructure (interceptors, drain inlets) in adequate condition to prevent exposure of underlying soil to runoff?

☒ ☐ ☐

Is accumulated sediment observed in the interceptors or drain inlets? If yes, note location and photograph.

☐ ☒ ☐

*Interceptors not accessed during this inspection. Drain inlets have inlet protection.*

Are corrective actions required?

☐ ☒ ☐

Attach a photograph of areas requiring corrective action.

☐ ☐ ☒

Describe any recent repairs/maintenance:

*None.*

Describe conditions and locations of the capping system which require attention:

*Gravel cover should continue to be monitored, and additional gravel placed as needed.*


Describe corrective actions required and their date(s) of implementation:

*None.*

## **APPENDIX D**

### **Upland Cap Survey Plat**





POINT TABLE							
PREVIOUS SURVEY (BY OTHERS)			SURVEY: MAY 9, 2017				DESCRIPTION
POINT #	NORTHING	EASTING	ELEVATION	NORTHING	EASTING	ELEVATION	
1	2163237.6800	6024596.4500		2163237.6800	6024596.4500		MONUMENT
2	2163265.8500	6023475.4900		2163265.8500	6023475.4900		MONUMENT
4	2159762.3530	6025316.9420	15.164	-	-	-	TBM
10	2163374.0390	6023319.3450	12.900	2163373.9523	6023319.3392	12.90	3A
11	2163375.5790	6023296.1160	13.010	-	-	13.01	3B
12	2164037.4320	6023374.6750	13.229	2164037.3606	6023374.5955	13.22	5A
13	2164036.1170	6023416.5070	13.160	2164036.0780	6023416.4014	13.16	5B
14	2164035.3860	6023450.0640	12.270	2164035.3260	6023450.0066	12.27	5C
15	2164470.1450	6023411.8380	11.550	2164470.1234	6023411.7101	11.55	6A
16	2164467.3940	6023443.1740	10.890	2164467.4160	6023443.1350	10.89	6B
17	2164536.6770	6023281.0150	12.200	2164536.6437	6023280.8983	12.20	7A
18	2164535.0830	6023328.3880	13.605	2164535.0237	6023328.2973	13.61	7B
19	2164531.9560	6023389.6420	13.500	2164531.9398	6023389.5164	13.50	7C
20	2164538.2420	6023219.0670	11.532	2164538.2420	6023219.0670	11.53	TBM SITE

- NOTES:**
1. ORIGINAL BASIS OF BEARINGS AND ELEVATION (DONE BY OTHERS): HORIZONTAL CONTROL IS BASED ON A MODIFIED CALIFORNIA COORDINATE SYSTEM. THE BASIS OF BEARING FOR THE MAP IS BETWEEN TWO BRASS DISKS WITHIN STANDARD CITY MONUMENT WELLS LOCATED AT THE INTERSECTIONS OF WRIGHT AVENUE WITH 4TH STREET AND 8TH STREET. THE COORDINATE VALUES AT 4TH STREET = NORTHING 2163265.85, EASTING 6023475.49. THE COORDINATE VALUES AT 8TH STREET = NORTHING 2163237.68, EASTING 6024596.45. VERTICAL CONTROL IS BASED ON TIDAL BENCH MARK STATION DISK STAMPED BM 2 1932, DESIGNATION BEING TIDAL 2 STA III 22 DESCRIBED AS A DISK SET VERTICALLY IN THE GRANITE FOUNDATION AT THE NORTHERN MOST ENTRANCE ON THE WEST SIDE OF THE OLD FORD PLANT. THE DISK HAVING AN ELEVATION OF 4.902 FEET MEAN LOWER LOW WATER (MLLW).
  2. HORIZONTAL CONTROL WAS ESTABLISHED USING THE PREVIOUS SURVEY'S CONTROL MONUMENTS DESIGNATED AS POINTS 1 AND 2.
  3. VERTICAL CONTROL WAS ESTABLISHED USING THE ONSITE TBM DESIGNATED AS POINT 20, BEING THE SW CORNER OF A CONCRETE VAULT WITH AN ELEVATION OF 11.532.
  4. POINT #11-3B WAS LOCATED UNDER EQUIPMENT, NORTHING AND EASTING WAS NOT ESTABLISHED. ELEVATION WAS TAKEN AT THE APPROXIMATE LOCATION.



**DILLON & MURPHY**  
CONSULTING CIVIL ENGINEERS  
ENGINEERING • PLANNING • SURVEYING  
847 N. CLUFF AVENUE, SUITE A2, LODI, CALIFORNIA 95240 (209) 334-6613

LEVIN RICHMOND TERMINAL

TOPOGRAPHIC SURVEY

RICHMOND, CALIFORNIA  
MAY, 2017

REV. NO.	DESCRIPTION	DATE	SCALE: AS NOTED	BENCH MARK: #20 EL: 11.532	SHEET
			DRAWN BY: SM	DESCRIPTION: SW CORNER OF CONCRETE STRUCTURE FOR SW#7, BASED ON PREVIOUS SURVEY, DONE BY OTHER.	1
			DESIGNED BY:		OF 1 SHEETS
			CHECKED BY: JM		JOB NO. 1749
			AS BUILT BY:		